



**Calhoun: The NPS Institutional Archive**  
**DSpace Repository**

---

Theses and Dissertations

1. Thesis and Dissertation Collection, all items

---

1979

Development of a microprocessor-based  
instrument for static testing small rocket engines.

Barber, Arthur Houghton

Monterey, California. Naval Postgraduate School

---

<http://hdl.handle.net/10945/18681>

---

*Downloaded from NPS Archive: Calhoun*



Calhoun is the Naval Postgraduate School's public access digital repository for research materials and institutional publications created by the NPS community. Calhoun is named for Professor of Mathematics Guy K. Calhoun, NPS's first appointed -- and published -- scholarly author.

**Dudley Knox Library / Naval Postgraduate School**  
**411 Dyer Road / 1 University Circle**  
**Monterey, California USA 93943**

<http://www.nps.edu/library>

DEVELOPMENT OF A MICROPROCESSOR-BASED  
INSTRUMENT FOR STATIC TESTING SMALL  
ROCKET ENGINES

Arthur Houghton Barber



# NAVAL POSTGRADUATE SCHOOL

## Monterey, California



# THESIS

DEVELOPMENT OF A MICROPROCESSOR-BASED  
INSTRUMENT FOR STATIC TESTING SMALL  
ROCKET ENGINES

by

Arthur Houghton Barber, III

September 1979

Thesis Advisor:

M. L. Cotton

Approved for public release; distribution unlimited.

T190312



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE  |                       | READ INSTRUCTIONS<br>BEFORE COMPLETING FORM                              |
|--|-----------------------|--|
| 1. REPORT NUMBER   | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER  |
| 4. TITLE (and Subtitle)<br>Development of a Microprocessor-Based Instrument for Static Testing Small Rocket Engines  |                       | 5. TYPE OF REPORT & PERIOD COVERED<br>Master's Thesis;<br>September 1979 |
|  |                       | 6. PERFORMING ORG. REPORT NUMBER   |
| 7. AUTHOR(s)<br>Arthur Houghton Barber, III  |                       | 8. CONTRACT OR GRANT NUMBER(s)   |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS<br>Naval Postgraduate School<br>Monterey, California 93940   |                       | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS              |
| 11. CONTROLLING OFFICE NAME AND ADDRESS<br>Naval Postgraduate School<br>Monterey, California 93940   |                       | 12. REPORT DATE<br>September 1979  |
|  |                       | 13. NUMBER OF PAGES  |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)<br>Naval Postgraduate School<br>Monterey, California 93940   |                       | 15. SECURITY CLASS. (of this report)<br>Unclassified                     |
|  |                       | 16a. DECLASSIFICATION/DOWNGRADING SCHEDULE                               |
| 16. DISTRIBUTION STATEMENT (of this Report)<br><br>Approved for public release; distribution unlimited.  |                       |  |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)   |                       |  |
| 18. SUPPLEMENTARY NOTES  |                       |  |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number)<br><br>Solid rocket testing                      Microprocessor Instrument<br>Static test stand                         Rocket engine testing<br>Pyrotechnics testing   |                       |  |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number)<br><br>A microprocessor-based instrument was developed for static testing solid-fuel rocket engines having peak thrusts of 130 Newtons or less and total impulses of up to 100 Newton-seconds. It measured peak thrust, total impulse, burn time, pyrotechnic delay time, and maximum casing external temperature, all to relative accuracies of two percent of the smallest expected values. This corresponds to better than 0.1 percent of |                       |  |

UNCLASSIFIED



UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

full scale. The instrument was designed for minimum parts cost and for portable operation from two twelve-volt batteries. It may be easily modified to test engines with five to ten times greater thrusts and total impulses.

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)





Approved for public release; distribution unlimited.

Development of a Microprocessor-Based Instrument  
for Static Testing Small Rocket Engines

by

Arthur Houghton Barber, III  
Lieutenant, United States Navy  
B.S., MIT, 1973

Submitted in partial fulfillment of the  
requirements for the degree of

MASTER OF SCIENCE IN ELECTRICAL ENGINEERING

from the

NAVAL POSTGRADUATE SCHOOL  
September 1979

Thesis  
B2165  
C1

## ABSTRACT

A microprocessor-based instrument was developed for static testing solid-fuel rocket engines having peak thrusts of 130 Newtons or less and total impulses of up to 100 Newton-seconds. It measured peak thrust, total impulse, burn time, pyrotechnic delay time, and maximum casing external temperature, all to relative accuracies of two percent of the smallest expected values. This corresponds to better than 0.1 percent of full-scale. The instrument was designed for minimum parts cost and for portable operation from two twelve-volt batteries. It may be easily modified to test engines with five to ten times greater thrusts and total impulses.



## TABLE OF CONTENTS

|      |  |    |
|------|--|----|
| I.   | INTRODUCTION-----                                  | 9  |
| II.  | DESIGN REQUIREMENTS-----                           | 12 |
|      | A. INPUT CHARACTERISTICS-----                      | 12 |
|      | B. CONSTRAINTS ON PARTS SELECTION-----             | 15 |
|      | C. ACCURACY REQUIREMENTS-----                      | 18 |
|      | D. NOISE MINIMIZATION-----                         | 20 |
| III. | TRANSDUCER AND ANALOG SYSTEM-----                  | 23 |
|      | A. THRUST TRANSDUCER DESIGN-----                   | 23 |
|      | B. AMPLIFIER AND FILTER DESIGN-----                | 30 |
|      | C. TEMPERATURE TRANSDUCER DESIGN-----              | 35 |
| IV.  | DIGITAL SYSTEM HARDWARE-----                       | 43 |
|      | A. INTERFACE CIRCUITRY-----                        | 43 |
|      | B. MICROPROCESSOR AND MEMORY SYSTEMS-----          | 48 |
|      | C. INPUT/OUTPUT CIRCUITRY-----                     | 54 |
| V.   | SYSTEM SOFTWARE-----                               | 60 |
|      | A. STRUCTURE AND GENERAL FEATURES-----             | 60 |
|      | B. SOFTWARE A/D CONVERSION-----                    | 65 |
|      | C. MAIN OPERATING PROGRAM-----                     | 67 |
|      | D. SUBROUTINES AND MINOR PROGRAMS-----             | 75 |
| VI.  | CONCLUSION-----                                    | 79 |
|      | APPENDIX A. CIRCUIT SCHEMATICS-----                | 81 |
|      | APPENDIX B. INSTRUMENT OPERATING INSTRUCTIONS----- | 88 |
|      | COMPUTER PROGRAM-----                              | 90 |



|                                |     |
|--------------------------------|-----|
| LIST OF REFERENCES-----        | 103 |
| INITIAL DISTRIBUTION LIST----- | 104 |





## LIST OF TABLES

|      |  |    |
|------|--|----|
| I.   | Characteristics of Design Inputs to System-----              | 12 |
| II.  | Characteristics of Transducer Beams<br>with Center Mass----- | 29 |
| III. | Amplifier Performance for Gain of 1000-----                  | 33 |
| IV.  | System Memory Map-----                                       | 51 |
| V.   | Decoding of LED/Comparator Select Lines-----                 | 57 |
| VI.  | Decoding of Data Routing Control Lines-----                  | 58 |
| VII. | Functions of Input Keys-----                                 | 61 |



## LIST OF FIGURES

|     |  |    |
|-----|--|----|
| 1.  | System Block Diagram-----  | 11 |
| 2.  | Example Shapes of Thrust-time Inputs-----                                | 13 |
| 3.  | Thrust Transducer-----   | 26 |
| 4.  | General Thermocouple Circuit Characteristics-----                        | 39 |
| 5.  | Four-bit Straight-binary Successive<br>Approximation A/D Conversion----- | 68 |
| 6.  | Flowchart of Main Operating Program-----                                 | 70 |
| 7.  | Thrust Transducer Amplifier and Filter Circuit-----                      | 81 |
| 8.  | Thermocouple Amplifier and Filter Circuit-----                           | 82 |
| 9.  | Thermocouple Compensation and Peak Detection<br>Circuit-----             | 83 |
| 10. | Digital Interface Circuit-----   | 84 |
| 11. | Microprocessor and its Support Circuitry-----                            | 85 |
| 12. | Memory System-----   | 86 |
| 13. | Digital Input/Output Circuit-----  | 87 |



## I. INTRODUCTION

The object of this thesis effort was to develop a minimum-cost, field-transportable instrument for static testing small solid-fuel rocket engines and accurately measuring several of their performance parameters. The system was specifically tailored to test model rocket engines for compliance with various state and Federal safety requirements and international standards for use in record attempts. For these purposes, measurements of total impulse, peak thrust, thrust duration, pyrotechnic delay duration, and casing external temperature were required, all to an accuracy of two percent of the peak value in each test. This instrument could be used with little modification to test any type of rocket engine having a thrust of 150 pounds or less and a total impulse of less than 200 pound-seconds.

The various parameters of interest here could certainly all have been measured with purely analog electronics. This could, for example, have been done by use of a multi-channel fast-response chart recorder. Such a recorder is very expensive and not easily portable, and its accuracy depends on proper selection of the scales to be used, which requires some advance knowledge of the performance expected from the test item. A microprocessor-based digital system has none of these disadvantages, and this is why the more complex digital design was used.



At the expense of some complexity in software, the system developed for this thesis delivered the required accuracy without advance scale selection when used to test a wide variety of rocket engines. In order to minimize parts costs, the system was developed as a single-purpose instrument rather than as an adaptation of an existing microcomputer.

The instrument consisted of a mechanical force transducer and a thermocouple temperature sensor, followed by analog amplifying and filtering circuits and a digital processing system. This microprocessor digital system performed analog-to-digital conversion, detection or computation of the values of the five parameters of interest, storage of the digital data representing thrust-vs.-time history, and display (under operator control) of the measured data. Figure 1 shows the relationship among the various components of the system.








Figure 1. System block diagram.



## II. DESIGN REQUIREMENTS

### A. INPUT CHARACTERISTICS

The engines which this system was designed to test come in a wide variety of powers, sizes, and durations, and have many different variations of thrust with time. Information on the general values of these parameters is not always available before a test, and even if it is not the parameters must be measured to an accuracy of two percent of their value. Consequently, this system was designed to have a maximum error of roughly two percent of the smallest value expected for each parameter. This gave it a performance on larger engines much better than the minimum requirements. The range of variation of each parameter which was used in establishing the design is given in Table I. Some typical shapes for the variations of thrust with time are given in Figure 2.

TABLE I  
CHARACTERISTICS OF DESIGN INPUTS TO SYSTEM

| Parameter          | Units          | Expected Values |         |
|--------------------|----------------|-----------------|---------|
|                    |                | Minimum         | Maximum |
| Peak Thrust        | Newtons        | 6.0             | 130.0   |
| Average Thrust     | Newtons        | 2.0             | 75.0    |
| Total Impulse      | Newton-seconds | 0.50            | 99.99   |
| Thrust Duration    | seconds        | 0.20            | 9.50    |
| Delay Duration     | seconds        | 0.00            | 15.00   |
| Casing Temperature | degrees C      | 25.0            | 250.0   |






Figure 2. Example shapes of thrust-time inputs.



Model rocket engines include a small gas-generating charge for activation of recovery systems, which may go off from 0 to 15 seconds after the propellant has burned out. The "thrust" spike which this produces on a test stand must not be considered when computing total impulse or peak thrust. With some types of engines there is an igniter-produced "thrust" spike prior to actual propellant ignition, and this must be ignored when computing thrust duration and total impulse. The system software had to be designed to perform both of these tasks.

A major consideration in the design of a digital data-collection system is the choice of a sampling rate. This rate must be at least twice the highest frequency component in the analog signal being sampled to avoid aliasing. The sampling rate has a great effect on the amount of memory required to store the samples and on the technique and hardware used in analog-to-digital conversion. Consequently, its selection was the first step in the design of the digital portion of this system. The natural frequency of the mechanical transducer used in this system was about 500 Hz, permitting sampling rates of up to 1000 Hz.

In order to determine the minimum acceptable sampling rate, the thrust transducer (described later) was built and was connected to an amplifier circuit and a variable-frequency four-pole low-pass filter. The direct output of the amplifier was connected to one channel of a Honeywell 906C





Visicorder recording oscillograph, and the filtered output was connected to a second channel. The recorder had flat frequency response to beyond 1000 Hz, and hence did not affect the results in this test. Various engines were fired in the transducer, and the recorder outputs before and after the filter were compared visually. The filter was set at various values from 500 Hz to 200 Hz. No significant change in the shape of the output by filtering was detected for any engine at any filter setting. Clearly the engine thrust variation contained no important information above 200 Hz and could safely be low-pass filtered at this value. A sampling rate of 500 Hz was chosen.

Casing temperature changes much more slowly than the other parameters measured by this system. Typically, it does not begin to rise until after the propellant has burned out, and does not reach its peak value until 30 to 70 seconds later. The sampling rate required for this parameter is not easily compatible with the high rate required for thrust sampling, so an analog peak detection circuit was used to hold the voltage corresponding to peak temperature for later one-time sampling by the digital system.

## B. CONSTRAINTS ON PARTS SELECTION

This system was designed to be field-portable, that is, operable from a pair of batteries connected to provide +12 V and -12 V with no more than one ampere of current drain on either battery. In addition, it was desired to minimize



the total parts cost even if this required a modest increase in software complexity and in hardware assembly time.

The voltage requirements posed no great difficulty, except in the selection of the analog-to-digital conversion hardware. Most A/D and D/A converters with the speed and number of bits required use either a +15V or a -15V power supply, or both. A suitable and inexpensive D/A converter was eventually obtained from Burr-Brown Research.

The current requirements dictated that Schottky low-power transistor-transistor logic (LS-TTL) be used in place of standard TTL in the digital circuit. CMOS logic was not used because of its incompatibility with many of the microprocessor system and other major special-purpose chips. The difference in price and speed between LS-TTL and standard TTL was too small to outweigh the major differences in current consumption. Current requirements also determined the choice of a liquid crystal display (LCD) for output rather than light-emitting diodes (LED). Although an LED display would have been substantially cheaper (\$9. versus \$20.) and slightly less complex, a four-digit display of reasonable size would have drawn at least 0.5 ampere and would have been unreadable in sunlight during field use. The reflective LCD that was chosen uses less than three milliamperes and is not affected by sunlight.

There were three major constraints on the selection of the microprocessor: cost, development system support, and complexity. Performance was not a major issue, since this



application was neither exceptionally fast nor dependent on large arithmetic computations. Nearly any eight-bit microprocessor would have had adequate performance. At the time that this project was undertaken, microprocessor development system (MDS) support was available at the Naval Postgraduate School for only three CPU chips: the Intel 8080A, the Zilog Z-80, and the Motorola 6800. Because of the complexity of the software required for this project, selection of a CPU not supported by a sophisticated MDS would have been unwise.

The features required from the microprocessor system were: 1) 15 or more I/O ports; 2) a programmable timer; and 3) 128 x 8 or more of static RAM (memory) for scratchpad and stack use. It was determined that such a system using the Z-80 would have used five chips and cost about \$55., while one using the 8080A would have used six chips and also cost \$55. A system using the 6802 (almost pin-for-pin compatible with the 6800) could be assembled with two chips for \$48., and this design was selected.

Parts cost was also a factor in the design of the analog amplifier section of this system, and in the selection of the analog-to-digital conversion technique. In both cases, single modules existed which would have met all of the performance requirements. Instead of a monolithic instrumentation amplifier for \$17., a set of three operational amplifiers (total parts cost \$5.) was used for each transducer. Rather than a fast monolithic 12-bit A/D converter module costing \$85., a good 12-bit D/A converter and a comparator were used



(parts cost \$30.) with idle microprocessor computing capacity being employed to generate successive approximation A/D logic. In both cases, the result was a system which met every performance requirement. The amount of effort expended in wiring and in software development to achieve this, however, was so great that the savings in parts cost was not justified.

Design of the RAM system for storing the thrust data from the analog-to-digital conversion was a final major area where cost and current requirements determined the design. A 16K x 4 or 8K x 8 memory was required. A static memory of this size using the most economical memory chips available would have cost about \$100. and consumed one ampere. The dynamic memory that was chosen cost \$55. and consumed 0.15 ampere. Once again, these savings were realized at the expense of added software complexity.

### C. ACCURACY REQUIREMENTS

Once the magnitudes of the expected inputs were defined, it was possible to calculate the accuracy required of the system as a fraction of full-scale values, and thus the number of bits of analog/digital conversion required.

The accuracy needed in peak thrust measurement was two percent of the minimum expected peak thrust (6.0 N), or 0.12 Newtons. Full-scale was 130 N, so on this basis the least significant bit in A/D conversion had to represent one part in  $130/0.12 = 1083$ . This is 10.1-bit accuracy.





Total impulse is simply the integral (digitally, the sum) of thrust with time, so its error is just the error in thrust multiplied by the duration of the thrust. A small thrust error in a long-burning engine can add up to a large total impulse error. However, if the thrust during this time is much larger than the error, the total impulse error will be only a small percentage. The error effect here depends on the average thrust of the engine. If thrust is measured to an accuracy of two percent of the minimum expected average thrust, then assuming no timer or arithmetic errors the total impulse error can never exceed two percent. Referring back to Table I, 2 percent of 2.0 N is 0.04 Newtons. This is the accuracy of thrust measurement that must be achieved to guarantee accuracy of total impulse to two percent of its minimum expected value, or,  $.02 \times .50 = .01$  N-sec. As a fraction of peak expected thrust, this requirement is  $130/.04 = 3250$ , or 11.7-bit accuracy. This more stringent requirement supersedes the 10.1 bits needed for peak thrust. A 12-bit conversion was chosen for thrust measurement.

For the temperature system, the maximum acceptable error was 3°C. There were nonlinearities and errors in the sensor itself (discussed later) which could introduce at least 2°C of error, so it was desired to hold A/D quantization error to 1°C or less. Since the maximum value was 250°C, this was one part in 250, or eight bits. For this system, only half of the -5V to +5V range of the A/D conversion input was used,



so relative to the full range nine bits of accuracy were required. Actually, the same twelve-bit system was used here as was used for thrust, and the last three bits were ignored.

Event duration timing in this system was done with a programmable timer driven by the system clock, which was crystal-controlled. The only error here was the 0.002-second quantization error, this being the interval between timer-produced interrupts. This was negligible.

#### D. NOISE MINIMIZATION

The system developed in this project was intended to be a highly accurate instrument. The accuracy requirements placed on it were such that its analog portion had to be capable of resolving microvolt signals from the transducers, and its digital portion had to have less than one-half bit of error in a 12-bit A/D conversion. This meant that careful attention had to be paid to noise minimization from the beginning of the design process. Reference 1 was a particularly useful source of design techniques for noise reduction. The design goal was a true-RMS noise voltage output of no more than 1/4 of the least significant bit value. For the thrust system, this was 0.6 millivolts. For the temperature system, it was 4.8 millivolts.

The ground system of the transducer and analog portion of the instrument was designed before the rest of the circuit. The entire instrument was built inside a covered metal chassis



to shield the circuits from external electric fields. This chassis was connected at only a single point to the other parts of the instrument's ground system. Ground conductors to all of the elements of the analog system were run from this central grounding point, with no more than two circuit elements being connected in series on the same conductor. This kept noise voltage from being induced in the ground of one element by the return current from another element flowing through the resistance of a shared ground wire.

Within all of the high-gain first-stage amplifier circuits, metal film one percent resistors were used to minimize thermal noise and drift. In addition to their anti-aliasing function, the low-pass filters at the outputs of the transducer amplifiers were used to eliminate high-frequency noise.

The cables between the circuit chassis and the transducers were twisted-pair conductors with braided metal shields. The shields were not used as signal conductors or grounds. They were isolated from system ground at the transducer end and connected to it at the chassis end, inside the chassis. When connected in this manner, the shields minimized noise coupling into the signal conductors from both ground loops and external electric fields.

The external +12V and -12V power supply inputs were bypassed to system ground with several parallel capacitors ranging from 10 microfarad electrolytic to .001 microfarad ceramic, to attenuate power supply noise over a wide frequency range. Within the system, separate heavily-bypassed



+5V and -5V power supplies were used for the digital and analog systems to prevent TTL switching noise from coupling into the analog elements.

In the digital portion of the instrument, a copper-clad circuit board was used to provide a good ground plane, which was connected to the system ground at one point with a large, flat conductor. Flat metal strips were used as digital power buses to provide maximum capacitive coupling to the ground plane, and hence minimum characteristic impedance  $Z_0 = \sqrt{L/C}$ . These buses were also bypassed to ground with large capacitors. The power leads of the TTL chips were all bypassed to ground with .015 microfarad capacitors to provide current for switching. Each TTL chip was connected to a power bus through its own unshared conductor.





### III. TRANSDUCER AND ANALOG SYSTEMS

#### A. THRUST TRANSDUCER DESIGN

The key step in the design of this instrument system was the selection of a technique for converting rocket engine thrust to an electrical signal. Each of the many types of device that are used as force-to-signal transducers has different requirements for output processing circuitry, so the design of this circuitry must await selection of the transducer. The transducer for this system had to meet the following requirements:

- 1) sufficient output to permit the .04 N minimum detectable thrust element to be converted to one bit in a 12-bit, 10-volt A/D conversion (2.44 millivolts) using an amplifier gain of no more than 1000,
- 2) ability to survive a force of 260 Newtons in case of an engine malfunction (explosion) during a test,
- 3) natural frequency of not less than 500 Hz with a 45-gram engine in place, to guarantee that transducer frequency response effects would not obscure the performance of engines under test,
- 4) ability to withstand prolonged exposure to corrosive engine exhaust gases;
- 5) low power consumption and minimum cost.

Although a wide variety of techniques are available for force transduction, relatively few of them could meet the frequency response and dynamic range requirements of this system. The high cost of suitable commercially-available units made it desirable to use a transducer that could be



built locally. Most such transducers contain a mechanical element which is deflected by the force, with this displacement leading to a change in the resistance, capacitance, or inductance of some attached device or to the deflection of a light beam. Of these techniques, strain gauges (which change resistance) are the least complex and the cheapest. It was decided to try these first.

Many commercial and laboratory force-sensing systems are based on strain gauges, so the techniques for their use are well developed. These gauges are extremely thin grids of copper or constantan which are adhesively bonded to a surface. As the surface deforms under the application of a stress, the gauge metal deforms and changes resistance. The fractional change in resistance, and hence in the output, is proportional to the mechanical strain,  $\Delta R/R = g\epsilon$ , where  $g$  is the gauge factor of the strain gauge (usually approximately 2.1) and  $\epsilon$  is the fractional elongation of the material, or the strain,  $\epsilon = \Delta l/l$ . As long as the thermal expansion coefficient of the gauge material is matched to that of the surface to which it is applied, thermal gradients will have little effect on gauge accuracy. By arranging two or four gauges on the test item so that equal numbers are in tension and compression, and by wiring them in a Wheatstone bridge arrangement, the electrical output of the gauges is maximized and thermal expansion errors are further reduced. This is discussed in detail in Ref. 2.




The mechanical element to which the gauges are bonded totally determines the linearity, magnitude, and frequency response of their output. The shapes that can be used for this element include rings, tubes, rods, octagons, and cantilevers. The rectangular cross-section cantilever is the easiest to analyze and fabricate, so it was the first choice. Cantilevers may be rigidly supported either on just one end (clamped-free) or on both (clamped-clamped). Both types were examined, and the clamped-clamped design was chosen because it had a higher natural frequency for a given level of strain output.

The equation for the stress in a cantilever as a function of its dimensions and material properties and the force  $F$  applied at its center was obtained from Ref. 3. Of particular importance is the linear relationship between input (force) and output.

$$\sigma = \frac{3Fl}{4bh}$$

The dimensions  $l$ ,  $b$ , and  $h$  are illustrated in Figure 3. Equations were also required which predicted the natural frequency of the beam, since this was a major design parameter. These are given in handbooks such as Ref. 3 only for beams without attached masses, whereas the transducer beam had an engine holder and engine in its center. An approximate solution was developed from the known no-mass natural frequency formula and from the general principle that





ALL STRUCTURAL PARTS ARE ALUMINUM




Figure 3. Thrust transducer.





natural frequency  $\omega_n$  is related to a beam's distributed mass  $m_b$  and spring constant  $K$  by:

$$\omega_n = \sqrt{\frac{K}{\alpha m_b}} \quad , \quad m_b = \rho b h l, \quad K = \frac{16 E b h^3}{l^3}$$

where  $\alpha$  is a constant. The exact equation for the fundamental frequency of an unloaded clamped-clamped cantilever was obtained from Ref. 3 as:

$$\omega_n = \frac{127.6 h}{l^2} \sqrt{\frac{E}{\rho}}$$

All units are pounds and inches.  $E$  is Young's modulus for the material used and  $\rho$  is its density.

These equations were set equal, and the value of  $\alpha$  was found to be  $\alpha = .0009827$ . It was then assumed that when a point mass  $m_c$  was added at the center of the beam, the natural frequency would become:

$$\omega'_n = \sqrt{\frac{K}{\alpha m_b + m_c}}$$

By examining the equations for stress and natural frequency together, it is apparent that tradeoffs are required in getting both the desired strain  $\epsilon = \sigma/E$  and natural frequency  $\omega'_n$ . Increasing Young's modulus by choice of the beam material will increase  $\omega'_n$  and reduce  $\epsilon$ . Increasing beam length  $l$  will increase  $\epsilon$  but sharply reduce  $\omega'_n$ . Increasing beam thickness  $h$  will increase  $\omega'_n$  but



sharply reduce  $\epsilon$ . Increasing beam width  $b$  will reduce  $\epsilon$  and not affect  $\omega'_n$ . In general, high strain  $\epsilon$  means low natural frequency  $\omega'_n$ .

Clearly, a minimum width and length beam was desired. However, enough width had to be provided to permit strong bolt attachment to supports at the ends. Also, enough length had to be allowed for development of a reasonable strain at the strain gauges, whose centers could be no closer than about 0.25" to the ends of the beam. A width  $b = 0.5$ " and a length  $l = 4.5$ " were selected on this basis. Using four strain gauges in a Wheatstone bridge with two in tension and two in compression, the output is:

$$\frac{\Delta V}{V_0} = \frac{\Delta R}{R} = g\epsilon = g\frac{\sigma}{E} = \frac{3Fgl}{4Eb^3h^2}$$

In order to avoid excessive current drain and reduced gauge lifetime from heating, it was decided to limit the DC bias voltage applied to the bridge to  $V_0 = 12V$ . Assuming that an amplifier with gain  $G = 1000$  was to be used on the bridge output, values of thickness  $h$  were found for various materials which gave the design condition of  $G\Delta V = 2.44$  millivolts for  $F = 0.04N = 0.009$  pounds.

$$\Delta V = \frac{3FV_0Gl}{4Eb^3h^2} = \frac{1530.9}{Eh^2} = .00244$$

Only standard thicknesses (1/8", 3/16", etc.) were considered. Each design was then checked to ensure that the stress was



below the yield stress of the material for  $F = 260 \text{ N}$ , and the natural frequency was calculated for a mass  $m_c = 60 \text{ grams}$  at the center of the beam. The results are summarized in Table II.

TABLE II

CHARACTERISTICS OF TRANSDUCER BEAMS WITH CENTER MASS

| Material            | Yield Stress<br>psi | E<br>psi           | $\rho$<br>lb/in <sup>3</sup> | Thickness<br>in | Frequency<br>Hz |
|---------------------|---------------------|--------------------|------------------------------|-----------------|-----------------|
| Aluminum (7075-T6)  | 67,000              | $10.4 \times 10^6$ | .101                         | .1875           | 630             |
|                     |                     |                    |                              | .250            | 953             |
| Steel (C1020)       | 48,000              | $30.0 \times 10^6$ | .272                         | .125            | 559             |
| Magnesium (AZ31B)   | 24,000              | $6.5 \times 10^6$  | .064                         | .250            | 773             |
| Titanium (Alloy 16) | 160,000             | $16.8 \times 10^6$ | .164                         | .1875           | 775             |

Although magnesium and titanium beams both were highly desirable because of their natural frequency, it was impossible to obtain a supply of either material. The final design used 0.1875" thick 7075-T6 aluminum, this thickness being chosen rather than 0.25" despite its lower natural frequency to ensure adequate sensitivity. The construction of the transducer is shown in Figure 3. Four Micro-Measurements EA-13-125BB constantan foil strain gauges were used, one on each side of the beam at each end, as close as possible to the clamping points to maximize the strain they saw. The beam could withstand an applied force of 1500 N (350 pounds) before yielding.



After the beam was built, a 48-gram mass was placed in the 12-gram engine holder to give  $m_c = 60$  grams, and the holder was tapped with a hammer. The output (after amplification) was observed on an oscilloscope to measure the natural frequency, which is approximately the frequency of the oscillatory response to this "impulse" input. This frequency was 526 Hz, or 83% of the predicted 630 Hz.

As a final test of the beam transducer, it was loaded with varying amounts of calibration weights (up to 18 pounds) and its amplified DC voltage output was measured for each weight. This output was exactly linearly related to the input force.

## B. AMPLIFIER AND FILTER DESIGN

The output signal from the transducer strain gauge bridge was a very small voltage--on the order of microvolts normally--superimposed on a 6 VDC common-mode voltage. The analog-to-digital conversion system could handle inputs over the range of -5V to +5V, so to take full advantage of its accuracy considerable amplification of the differential output across the bridge was necessary. The literature on instrumentation-type DC amplifiers [Refs. 4-6] recommends that gains of greater than 1000 be avoided, if possible. Since maximum gain was desirable to permit a high transducer natural frequency, the design problem was reduced to finding the most cost-effective 1000-gain DC amplifier.





There are many figures of merit used to judge the performance of an instrumentation-type amplifier. In this relatively high-gain, low-frequency application, the important ones were the following:

- 1) input impedance ( $Z_{in}$ )
- 2) input noise voltage
- 3) common-mode rejection ratio (CMRR)
- 4) input offset voltage ( $V_{os}$ )
- 5) input offset current ( $i_{os}$ )
- 6) input offset current and voltage thermal drift.

High input impedance was desired to minimize the current drawn by the amplifier from the transducer. This current could induce an error voltage in the resistance of the strain gauges. Input noise voltage is amplified by the gain of the amplifier and appears at the output, where no more than 0.6 millivolts (RMS) of noise could be tolerated. Assuming that the output was to be limited to a noise bandwidth of 250 Hz, then:

$$V_{n \text{ out}}(\text{RMS}) = \sqrt{\text{Gain} \cdot \text{Bandwidth} \cdot G_n} =$$

$$V_{n \cdot in} \sqrt{\text{Gain} \cdot BW}$$

$$0.0006 = V_{n \cdot in} \sqrt{1000 \cdot 250}$$

$$V_{n \text{ in}} \leq 1.2 \mu\text{V}/\sqrt{\text{Hz}}$$

Here  $G_n$  is input noise power spectral density. The maximum acceptable noise input voltage was 1.2 microvolts per  $\sqrt{\text{Hz}}$ .



Input offset voltage is the difference between inverting and non-inverting input voltages seen by the amplifier internally when both input terminals are grounded. When multiplied by the gain, it appears as an output DC voltage offset. In order to avoid large output offsets, it was desired that this input offset be no more than two millivolts. More important than the absolute value of this voltage was its variation with temperature. The lowest possible variation was desired, to avoid large drifts in output resulting from small short-term fluctuations in temperature inside the instrument circuit. Input offset current, when multiplied by the equivalent DC resistance of the circuit's inverting input and by the gain [Ref. 4], becomes an output offset voltage, so a minimum value and drift of this quantity was also desirable. As discussed in the calculations for noise input voltage, a gain-bandwidth product of at least 250,000 was required from the amplifier. Since an output voltage range of ten volts was needed, the slew rate  $S$  had to be [Ref. 4]:

$$S \geq 2\pi V_{\text{out}} F_{\text{max}} = .016 \text{ volt}/\mu\text{sec}$$

A high common-mode rejection ratio was desirable to minimize the effects on the amplifier of fluctuations in the DC offset of the transducer output.

Once the figures of merit for selection were established, manufacturers' data was consulted to find devices which met the performance requirements. Those which did so fell into



three categories: operational amplifiers with FET inputs; op amps with supergain bipolar transistor inputs; and monolithic instrumentation amplifiers. An amplifier system made from discrete op amps requires three of these devices, while monolithic amplifiers do the same job with a single (more expensive) chip.

Most of the acceptable op amps and amplifiers were extremely expensive and had long delivery times. On the basis of cost alone, the field was quickly narrowed to the National LM308A bipolar op amp (\$1.25) and the Analog Devices AD521J monolithic amplifier (\$13.). Performance figures for these two devices are summarized in Table III. The LM308A was selected because of its superior noise and offset voltage performance and because it gave a lower system parts cost, even though three chips plus ten resistors and capacitors were required for this approach compared to one chip and two resistors for the AD521J.

TABLE III  
AMPLIFIER PERFORMANCE FOR GAIN OF 1000

| Device | $Z_{in}$<br>$M\Omega$ | Output Noise<br>mV | Bandwidth<br>Hz | $V_{os}$<br>nV | $V_{os}$ Drift<br>$\mu V/^{\circ}C$ | CMRR<br>dB |
|--------|-----------------------|--------------------|-----------------|----------------|-------------------------------------|------------|
| LM308A | 40                    | .02                | 600             | 0.73           | 2.0                                 | 110        |
| AD521J | 3000                  | 1.20               | 6000            | 2.00           | 7.0                                 | 110        |



Once the device to be used was selected, design of the amplifier circuit was straightforward. A standard op amp circuit was selected from Ref. 5 and the appropriate values of resistances were calculated to deliver the required gain. The circuit is shown in Figure 7, Appendix A. This design had the advantage that its input impedance was virtually infinite. Since the inverting and non-inverting inputs go to separate op amps,  $Z_{in}$  is twice the impedance from one input to system ground. The circuit amplifies only differential input voltages,  $V_1 - V_2$ , not any common-mode voltage. The gain equation is:

$$A_V = \frac{V_0}{V_1 - V_2} = - \left(1 + \frac{2R_1}{R}\right) \left(\frac{R_0}{R_2}\right)$$

It was known that a low-pass filter with DC gain of 2.57 would be used on the output, so the instrumentation amplifier gain needed was  $1000/2.57 = 389$ . Because of the limited selection of resistance values available, a theoretical gain of 402 had to be used in the final design. Metal film 1% resistors with relatively low values of resistance were used for noise minimization, accuracy, and thermal stability.

The amplifier circuit was followed by a four-pole, 200-Hz Butterworth low-pass filter, which provided anti-aliasing for the 500 Hz A/D conversion sampling and attenuation of higher-frequency noise. This filter was designed, using the techniques described in Ref. 7, as a cascaded pair





of two-pole active filters. The design DC gains of the two filter stages were 2.235 and 1.152. The filter was made using LM308 op amps, a less expensive version of the LM308A with higher voltage and current offsets. Carbon resistors were used. The precision components used in the instrumentation amplifier were not necessary here because of the low gain and high input voltage levels involved. Based on the measured values of the resistors actually used in this filter, its expected gain was 2.535, giving an overall DC gain for the amplifier system of 1019. The low-pass filter is also illustrated in Figure 7 of Appendix A.

Once the amplifier and filter were built, the system's gain and frequency response were measured by applying a variable frequency sinusoidal signal to the input through a 200:1 voltage divider and measuring the signal and output voltages with an AC voltmeter. An overall gain of 992 was measured, and the 6 dB rolloff point of the four-pole filter was 205 Hz. The strain gauge bridge was then connected through the shielded cable system, and a true-RMS voltmeter was used to measure the noise output voltage after the filter. This was 0.6 millivolt. All values were quite close to the desired performance.

### C. TEMPERATURE TRANSDUCER DESIGN

The requirement of measuring the surface temperature of a rocket engine casing to an accuracy of  $3^{\circ}\text{C}$  over the range  $25\text{-}250^{\circ}\text{C}$  demanded a second transducer system. There are



only two reasonably simple and accurate techniques for converting a surface temperature to a voltage signal: resistance thermometers (thermistors) and thermocouples. The procedures for using both are highly developed and their errors are well understood. Reference 8 contains a great deal of data on surface thermometry and was used extensively in the development of this transducer.

Most types of thermocouples and thermistors have outputs (voltages or fractional change in resistance, respectively) which are not linearly related to temperature, except over fairly narrow ranges. This makes their implementation in an accurate, wide-range digital system fairly difficult; the conversion from transducer signal to displayed temperature requires some sort of table look-up or a nonlinear conversion equation. The primary selection criterion for this transducer was linearity of output over a wide temperature range. All types of thermistors and thermocouples require analog processing circuitry of roughly equal complexity, and their accuracy and response times depend more on their size and the technique of installation than on inherent properties, so these factors were not considered in the selection.

The data for numerous commercial thermistors and the standard voltage-vs.-junction temperature tables [Ref. 9] for the popular combinations of thermocouple metals were examined for linearity over the desired temperature range. Of these, the chromel-alumel thermocouple was by far the



most nearly linear. It produces an average output of  $40.725 \mu\text{V}/^\circ\text{C}$  over the range  $25\text{-}250^\circ\text{C}$ , with a maximum deviation from linearity of  $31.0 \mu\text{V}$  at  $120^\circ\text{C}$ . Thus, by assuming that its output and input were linearly related, a maximum error of less than one degree was introduced.

Since it was desired to make the A/D conversion of temperature nine bits with respect to a 10 V output range, the least significant bit (corresponding to one degree C) was  $10/2^9 = 19.531$  millivolts. This meant that the thermocouple output signal had to be amplified by  $19.531 \times 10^{-3} / 40.725 \times 10^{-6} = 479.6$  before conversion. An op amp amplifier system identical in design to that on the thrust transducer was used, with a two-pole low-pass Butterworth filter. Since temperature was to be sampled only one time, anti-aliasing was not a major concern; the principal purpose of the filter was noise reduction and a less expensive one with only two poles was acceptable. The DC gain of a two-pole Butterworth filter is 1.586, so the design gain of the amplifier was  $479.6/1.586 = 302.4$ .

The amplifier/filter circuit is shown in Appendix A, Figure 8. Once it was built, its gain was tested in the same manner as described for the thrust amplifier. A trimming potentiometer was placed in parallel with one of the filter resistors so that overall gain could be adjusted to achieve exactly the required value of 479.6. This was necessary to achieve the desired temperature accuracy. Once this was



done, the output noise after the filter was measured with the thermocouple and cabling connected, using a true-RMS voltmeter. The maximum acceptance noise was 4.8 millivolts; the measured value was 0.3 millivolts.

Thermocouples work on the principle that a junction between dissimilar metals produces a contact voltage which is related to temperature. This occurs at every such junction in a thermocouple system, not just at the sensor junction. Figure 4 shows the connection of a general thermocouple circuit. Each junction may be modeled as a voltage source whose value depends on the materials involved and on the temperature. If intermediate junctions  $J_3$  and  $J_4$  between the thermocouple wires and the copper conductors of the amplifier system are at the same temperature, then their voltages cancel. If reference junction  $J_2$  is not explicitly provided, then since  $J_3$  and  $J_4$  are invisible a virtual reference junction between materials A and B will exist at the amplifier leads, at their unknown temperature.

The input to the amplifier is proportional to the difference in temperature between sensor and reference junctions, not to the sensor temperature alone. Clearly, the reference junction temperature must be known very accurately. This is usually achieved by immersing it in an ice bath, but this was considered impractical for a field-portable system. An alternate solution is to add a system to the circuit which changes output voltage with temperature at exactly the same rate as the reference junction, but in the opposite direction








Figure 4. General thermocouple circuit characteristics.



so that the sum of the two voltages is a constant as ambient temperature varies. This technique was chosen, with the compensation being placed after the amplifier.

The compensation system used was a Yellow Springs Instrument Co. YSI 44202 precision thermistor network, whose output voltage was:

$$V_{out} = 0.805858 V_{in} - 0.0056846 V_{in} T_T$$

where  $T_T$  is the thermistor temperature. The amplified output of the thermocouple was:

$$V_{out} = 0.019531 T_S - 0.019531 T_R$$

where  $T_S$  is the sensor thermocouple temperature and  $T_R$  is the reference thermocouple temperature.

The thermistor network was connected to a  $V_{in} = +5$  VDC power supply, and was combined with the thermocouple system output and with a DC source in an op amp summing network. By appropriate choice of the fixed scaling resistors in this summer, these three signals were made to produce the sum:

$$V_{out} = -0.01953 T_S + 0.01953 T_R - 0.01953 T_T$$

The reference thermocouple and the thermistor were then placed close together in a remote section of the circuit chassis so that  $T_T = T_R$ , leaving the output voltage directly proportional to the sensor thermocouple temperature. This circuit was checked by immersing the sensor in an ice bath ( $0^\circ\text{C}$ ) and adjusting a trimmer potentiometer on the fixed input to the summer until the output was  $-0.40$  V. The sensor



was then immersed in boiling water (100°C). The output was -2.35 V, as predicted. The response was quite rapid.

A non-inverting negative peak detector circuit [described in Ref. 4] was placed at the output of the summer to catch and hold the most negative output value, corresponding to the highest temperature. After some experimentation, it was found that a 25  $\mu$ F holding capacitor was required in this circuit to minimize the voltage droop from leakage through the op amp circuit during a 75-second hold time. For most rocket engines, the maximum casing temperature is not reached until 60 to 70 seconds after the start of a test and in these normal cases voltage droop during the remaining 5 to 15 seconds of the holding period was negligible with this capacitor. The compensation system and peak detector are shown in Appendix A, Figure 9.

Following the guidelines in Ref. 8 for minimizing the error in surface temperature measurement, the thermocouple sensor was made from small-diameter (28 AWG) wire. The chromel and alumel wires were soldered close together and parallel for more than 100 wire diameters on a very thin piece of brass shim stock 0.25" square. This piece was formed to the shape of the engine casing surface with the wires paralleling what were estimated to be isotherms, and was covered with insulation before being taped tightly to the surface in a test. No measurements of error were conducted, but despite the care taken in the design an error



of two degrees was the minimum that was expected. This was in addition to the one degree error from A/D conversion.





#### IV. DIGITAL SYSTEM HARDWARE

##### A. INTERFACE CIRCUITRY

The signals developed by the thrust and temperature transducers and their associated amplifier, filter, and compensation systems were analog voltages with well-determined characteristics. The primary processing and decision-making done by this instrument was done with digital logic on the digital representation of these signals. A sample-and-hold circuit, a digital-to-analog converter, and a group of comparators, collectively referred to here as the interface circuitry, was used to link the analog and digital systems. Reference 10 was particularly helpful in designing this circuitry.

There were two independent transducer analog signals in this system that required analog-to-digital conversion. These conversions did not have to be simultaneous, and could have been done with two independent A/D converters, with one converter using multiplexed analog inputs, or with one converter using multiple inputs and outputs. The use of multiple A/D converters or even single monolithic A/D converters was rejected on the basis of parts cost. Multiplexing analog signals to the accuracy required by this system is quite difficult and was not considered desirable. Once the decision was made to use surplus microprocessor computing capacity



to perform A/D conversion with a D/A converter, it became possible to use the last method and put together a conversion system with multiple independent inputs and nonsimultaneous outputs.

The first step in designing the conversion system was selection of a D/A converter. Since only one converter was to be used for both transducers, the specifications were determined by the more demanding application, the thrust conversion. In this case, 12 bits of resolution with 11.7 bits of accuracy were required. This conversion could have taken as long as one millisecond or so; some part of the two-millisecond interval between conversions (500 Hz sampling rate) had to be left for the microprocessor to do other computation. With this amount of time available, the settling time of the D/A converter was not important. The accuracy requirement meant that the analog output of the converter could not deviate from a straight line between its minimum and maximum values by more than 30 percent of the least significant bit voltage, or 0.73 mV. This is called "0.3 LSB linearity."

The combination of 0.3 LSB linearity and operability from 12 V power supplies proved to be impossible to find among reasonably-priced 12-bit D/A converters. The linearity requirement was relaxed to 0.5 LSB, making one converter acceptable: the Burr-Brown DAC-80Z-CBI-V. This device had the additional advantages of being a monotonic converter



rather than a multiplying type, meaning that it did not require an external precision reference voltage, and of being a voltage rather than current output device, meaning that no external buffer op amps were required on its output. It used complementary binary input, with an all "0" digital input giving the most positive analog output and an all "1" input the most negative output. The converter could be connected to produce a variety of voltage output ranges; -5V to + 5V was the one used. Gain and offset trimming potentiometers were required to obtain exactly the correct output voltage range. The settling time was three microseconds.

The A/D conversion technique employed was successive approximation. This is commonly implemented in hardware in fast A/D converter chips, but it is quite susceptible to slower software implementation as well. Basically, the microprocessor was used to generate a 12-bit test digital value which was then sent to the DAC. The resulting analog output from the DAC was sent to one input of an analog comparator while the signal voltage being converted was held at the other input. The microprocessor then sampled the output of the comparator and modified the test value according to whether the output was a digital "1" or a digital "0", i.e., whether the test value was greater than the signal or less. The program to do this is described in Chapter V. Twelve such successive tests are needed to perform a 12-bit conversion, requiring about 700 microseconds with the program used in this system.



Multiple independent outputs were obtained by sending the DAC output voltage in parallel to several comparators, with the second inputs to each comparator going to different analog signals. The microprocessor selected the output of one comparator for monitoring at the beginning of each conversion by sending the appropriate digital select code to a gated R-S flip-flop. The R output of this flip-flop caused the thrust comparator output to be transmitted through an AND-OR-INVERT circuit to the microprocessor input port, and blocked the temperature comparator output. The S output did the reverse.

The accuracy of the A/D conversion scheme was measured by applying DC voltages to a comparator input and recording the digital output of the system, then converting this digital value back to its analog equivalent. The difference between the actual voltage and its analog equivalent was the error. Over the full  $\pm 5$  V range of inputs, the standard deviation of error was 5 mV. This corresponds to 11 bits of actual delivered accuracy. While less than the desired 11.7 bits, this was considered still acceptable. The basic reason for this inaccuracy was the width of the comparators' switching transition.

The comparators were LM308 op amps operated open-loop and connected to  $\pm 5$  V power supplies. These devices have an open-loop gain of  $3 \times 10^5$ . This means that their output voltage is greater than the difference between their inverting and non-inverting input voltages by this factor, up to





the limiting point where the output equals a power supply voltage. The output will thus swing over its full range of ten volts in response to a change of  $10/3 \times 10^5 = 0.33 \text{ mV}$  in the differential input voltage. Since these comparators were connected to TTL-compatible circuitry, a feedback diode was added to limit the negative output to  $-0.3 \text{ V}$ . The slope of this diode's forward-bias characteristic caused a broadening of the comparator's transition region between output levels. These comparators were connected with the non-inverting input grounded through a resistor and the inverting input connected to the two voltages being compared through identical resistors. This is equivalent to connecting each input to one of the voltages, and it eliminates the error effects of offset currents, as discussed in Ref. 4. The switching time of the comparator was about ten microseconds.

Successive approximation A/D conversion is extremely dependent on having the voltage under conversion held constant to within one or two LSB throughout the process. If this is not done, gross errors may result. This was not a problem with the slowly-changing peak detector output from the temperature transducer, but the thrust transducer voltage could change so rapidly that a sample-and-hold circuit was necessary between it and the A/D conversion system. What was required was a sample-and-hold having less than one LSB ( $2.44 \text{ mV}$ ) droop during the two-millisecond interval between thrust voltage samples, and having acquisition and settling times of a few microseconds or less. A Datel SHM-LM-2 was



available and met all of these requirements, so it was used. With a 1000 pF holding capacitor, this device had an acquisition time of six microseconds (to 0.01%), a settling time of 0.8 microseconds, and a droop of 0.1 mV in 2 milliseconds. A polystyrene holding capacitor was used to minimize errors due to dielectric absorption.

The interface circuitry is illustrated in Appendix A, Figure 10.

## B. MICROPROCESSOR AND MEMORY SYSTEMS

The key elements of the digital portion of this system were the Motorola 6802 microprocessor and the MOS Technology 6530-002 input/output/timer chip. The remaining major elements of the digital system provided either memory or input/output support for these two devices.

The 6802 is an eight-bit microprocessor with an address space of 64K bytes (16 address lines), an on-chip RAM memory of 128 bytes, and an on-chip clock oscillator which permits clock rates of up to one megahertz, depending on the value of an external crystal. It has the same instruction set as the Motorola 6800 and is almost pin-for-pin compatible with it. It requires only a +5V power supply. The microprocessor and its supporting circuitry is shown in Appendix A, Figure 11.

Proper operation of the 6802 was found to depend on close adherence to the correct power-up sequence. The RESET input had to be held below 0.8 V for at least 20 milliseconds after



the chip's  $V_{CC}$  power supply went above 4.75 V, and then had to transition sharply and without oscillation to +5 V. This was accomplished with a comparator circuit identical to those described in the previous section of this chapter. A constant -2.5 V was obtained from a resistive voltage divider connected to the analog circuit - 5V supply and applied to one comparator input, while the second input was obtained from a series RC circuit connected between the digital +5V supply and ground. This circuit took 30 milliseconds to charge to +2.5 V after digital power was turned on, at which point the comparator output went high, setting the 6802 RESET.

The 6530 is a multipurpose microprocessor support chip. It has 64 bytes of RAM and 1024 bytes of mask-programmed ROM (neither of which were used in this system), and a programmable timer. It also has 16 input/output ports, arranged in two groups of eight called peripheral registers A and B (PA and PB). Each individual port of each register may be set up as a direct input or as a latched output by writing a "0" or a "1", respectively, to the corresponding bit of two registers called data direction registers A and B (PAD and PBD). Each of these four registers has a unique address derived from the chip's ten address lines and two chip select lines. Three of the I/O ports (PB5-7) were used as chip selects or as interrupt outputs, leaving 13 ports available for this system.

The 6530's timer is a series of eight registers located at adjacent addresses. The timer counts down for a number



of clock cycles equal to 1, 8, 64, or 1024 times the 8-bit value loaded in the appropriate register, and can generate an interrupt on the IRQ pin (PB7) when the count reaches zero. It was used in this system to provide a master event-timing reference by generating a non-maskable interrupt (NMI) to the microprocessor every two milliseconds. This 6530 IRQ pin was connected to the NMI input of the 6802 through a one-shot set to provide a five-microsecond low pulse. Considerable difficulty was experienced when interrupts were applied to the microprocessor directly rather than through a short-pulse one-shot. The 6802 would often execute the register-stacking operations of its built-in interrupt service routine, reach the first step of the software interrupt service program and then repeat the register stacking if the interrupt was still set. If the interrupt source was a type that remained set until cleared by a command in the service program, the 6802 remained locked in this cycle indefinitely.

The 6802 and 6530 are designed to drive a maximum of one TTL unit load on each pin. Those 6530 I/O pins which were used for output, and several of the 6802 address and control signal pins, had to be connected to larger loads than this. These pins were buffered with 74LS367 non-inverting buffers to increase their drive capacity to five unit loads.

The program memory for this system was quite simple. The 128 bytes of RAM which were built into the 6802 were used for stack and for program working storage. This RAM was located on "page zero" of the microprocessor's address space,





at addresses 0000-007F. The overall map for all of this system's memory, and for the various memory-mapped I/O and timer registers, is presented in Table IV. The operating program was stored in two 2708 UV-erasable programmable read-only memory (EPROM) chips, each having a capacity of 1024 8-bit bytes. These were wired to be at the top of the address space, at F800-FFFF. Their requirement for +12 V, +5V, and -5V power supplies was not a problem since these voltages were already required by several other circuit elements. The memory circuit for this system is illustrated in Appendix A, Figure 12.

TABLE IV  
SYSTEM MEMORY MAP

| Address |      | Chip | Function                      |
|---------|------|------|-------------------------------|
| START   | END  |      |                               |
| 0000    | 004F | 6802 | RAM; working memory           |
| 0050    | 007F | 6802 | RAM; stack                    |
| 1340    |      | 6530 | Peripheral register A; output |
| 1341    |      | 6530 | Data direction register A     |
| 1342    |      | 6530 | Peripheral register B; input  |
| 1343    |      | 6530 | Data direction register B     |
| 1344    | 134F | 6530 | Timer registers               |
| 13C0    | 13FF | 6530 | RAM; not used                 |
| 2000    | 5FFF | 2117 | Dynamic RAM; data storage     |
| F800    | FBFF | 2708 | EPROM-1; program storage      |
| FC00    | FFFF | 2708 | EPROM-2; program storage      |



The original design of this instrument included a requirement that all of the thrust A/D conversion output data be stored in memory. This data was to be used in several ways. The first was to compute corrections to the thrust and total impulse data to account for the effects of engine propellant weight loss during a test. When the thrust transducer is placed flat, engine weight and thrust act in the same direction and are indistinguishable. The weight loss during a test can be as great as 0.6 Newton for large engines, and this can integrate to a substantial but predictable total impulse error. The error can be reduced by placing the transducer on its side, so that the weight and thrust vectors are perpendicular and the weight loss changes only a torsional force, to which the strain gauge bridge is insensitive. A more flexible approach, and the one which was desired, is to measure the amount of weight loss by comparing the transducer zero outputs before and after a test. Using this, a linearly-varying correction (zero for initial thrust, maximum for final thrust) can be applied to each stored data point and the total impulse and peak thrust can be recalculated from the corrected data.

Other plans for the stored thrust data included using it to generate a video output of thrust versus time on either an oscilloscope or a television-type display, or both. None of these uses for the data were implemented by the time that this report was written, although all were still under development. Storage of thrust data was not necessary for



performance of the other instrument functions described in this report.

Since this system was required to take 500 samples of thrust per second for up to 9.5 seconds, 4750 12-bit data points had to be stored. The reasons for using dynamic rather than static memory for this were discussed previously. The most economical dynamic RAM available was the Intel 2117 16K x 1 chip. Since the thrust data was already available in four-bit words as a result of the A/D conversion process, it was decided to use four of these chips to form a 16K x 4 memory. Accomplishing the required data storage used  $3 \times 4750 = 14,250$  bytes of this.

Dynamic memory requires periodic refreshing to maintain its data. The 2117 chip is described in Ref. 11 as being arranged internally in a 128 x 128 array, and a refresh operation requires only that each of the 128 row addresses be written to every two milliseconds. The chip is a 16-pin package with only seven address input lines. These are multiplexed, serving as row address inputs during the first part of a read or write cycle and as column address inputs during the second part, giving effectively the 14 address lines required by a 16K memory. The refresh control and the address multiplexing was accomplished with a single dynamic RAM control chip, the Intel 3242. This took in 14 address lines, a clock, and a refresh enable line, and provided all the necessary address data to the 2117 chips for both refresh and normal read-write operations.



The 2117 required two timing inputs not provided by the 3242: row address strobe (RAS) and column address strobe (CAS). These enabled the chip to distinguish whether its address inputs were to be interpreted as row or column addresses. Both must appear with the proper time relationship during each read or write operation. They were derived from 6802 address and clock outputs, and effectively served as chip selects since they were gated so that they reached the memory chips only when the memory address was on the address bus. The 2117 has separate data inputs and outputs, and it was found that an extraneous signal appeared on the output in response to an address input regardless of the state of the  $\overline{WE}$  read-write control. Consequently, the data input and output could not simply be connected directly to the system data bus; each had to be isolated by a tri-state buffer which was enabled by  $\overline{WE}$  (for input) or by  $\overline{WE}$  complemented (for output).

### C. INPUT/OUTPUT CIRCUITRY

At an early stage of this system's design it was decided to make every effort to squeeze the required input and output (I/O) functions into the 13 ports available on a single 6530 chip. This decision was made to limit parts cost; it led to software complexity and debugging problems that more than offset the small savings in parts. The 13 I/O ports were allocated as follows:





|         |                                 |
|---------|---------------------------------|
| PB0     | input from comparators          |
| PB1-PB5 | input from 16-key keyboard      |
| PA0-PA2 | routing control for output data |
| PA3     | sample-and-hold control         |
| PA4-PA7 | output data to DAC, LED, LCD    |

The input from the comparators, PB0, was simply wired to the output of the comparator AND-OR-INVERT circuit discussed in section A of this chapter. The PA3 output for sample-and-hold control was wired directly to the appropriate pin on the SHC chip. The remaining I/O functions require more explanation. The I/O circuit is shown in Appendix A, Figure 13. The IC numbers used hereafter refer to this drawing.

A 16-key unencoded, debounced hex keyboard was used to select among the various operating modes and output data displays of this system. These keys were each SPST momentary switches, with one side of each tied to +5V and the other to one of the 16 inputs of a Harris HD-0165 keyboard encoder. Depressing a key pulled the corresponding encoder input high; the required pull-up resistors were built into the encoder. It also caused the encoder STROBE output to go low, setting a flip-flop (IC34) which was connected through a one-shot to the IRQ interrupt on the 6802 microprocessor. The 6802 looked at the keyboard output only in response to this interrupt, and cleared the interrupt flip-flop as part of its response. The four outputs of the encoder were held in latch IC35, whose enable circuitry allowed it to reject keyboard



outputs resulting from the simultaneous depression of two keys. This latch was reset only by the depression of a new keyboard key. Key debouncing was accomplished with a software wait loop.

Three single light-emitting diodes (LED) were used in this instrument to indicate its present status, and a four-digit liquid crystal display (LCD) was used to read out test data. The LED's were labeled TEST, CLEAR, and CALIBRATED, and their use is explained in the next chapter. They were driven by three of the seven outputs of a standard common-anode open-collector decoder-driver chip (IC32). The hex inputs to the driver required to achieve each desired combination of status lights are listed in Table V. These hex inputs were held for the decoder by a four-bit latch (IC36) which was reset only when a new sequence of status lights was commanded by the microprocessor.

The output data from the system's software was routed in four-bit words on I/O lines PA4-PA7 to eight possible destinations. These destinations were the four LCD digits, the 12-bit (three-word) input to the D/A converter, and a mixed destination which included a gated flip-flop for comparator selection and the LED decoder-driver. The selection of which of these destinations was to receive the data was made by output lines PA0-PA2, which were decoded into eight lines by a three-to-eight line decoder (IC40) and were then used as digit or chip selects or latch enables.



TABLE V  
DECODING OF LED/COMPARATOR SELECT LINES

| <u>HEX Inputs</u> | <u>Test</u> | <u>LED Selected</u> |                   | <u>Comparator Selected</u> |                    |
|-------------------|-------------|---------------------|-------------------|----------------------------|--------------------|
|                   |             | <u>Clear</u>        | <u>Calibrated</u> | <u>Thrust</u>              | <u>Temperature</u> |
| 1,3,7             | off         | on                  | off               | off                        | off                |
| 2                 | on          | on                  | off               | off                        | off                |
| 4,9               | off         | on                  | on                | off                        | off                |
| 5                 | off         | off                 | on                | off                        | off                |
| 6                 | on          | off                 | on                | off                        | off                |
| 8                 | on          | on                  | on                | off                        | off                |
| A                 | on          | off                 | off               | off                        | off                |
| B                 | off         | off                 | off               | off                        | off                |
| C                 | off         | on                  | on                | off                        | on                 |
| D                 | off         | off                 | on                | on                         | off                |
| E                 | on          | off                 | on                | off                        | on                 |
| F                 | off         | off                 | off               | on                         | off                |

A Schottky TTL decoder was used to ensure that the enable/select lines were stable before the data was sent to its destination. The data and select outputs left peripheral register A of the 6530 simultaneously, and the data lines were delayed by two 74LS367 non-inverting buffers to avoid a possible race condition. The decoding of lines PA0-PA2 is described in Table VI.



TABLE VI  
DECODING OF DATA ROUTING CONTROL LINES

| PA2 | PA1 | PA0 | Data Destination          |
|-----|-----|-----|---------------------------|
| 0   | 0   | 0   | low word of D/A converter |
| 0   | 0   | 1   | middle word of DAC        |
| 0   | 1   | 0   | high word of DAC          |
| 0   | 1   | 1   | LED/comparator select     |
| 1   | 0   | 0   | LCD digit 2               |
| 1   | 0   | 1   | LCD digit 1 (LSD)         |
| 1   | 1   | 0   | LCD digit 4 (MSD)         |
| 1   | 1   | 1   | LCD digit 3               |

The liquid crystal display was a Timex T1001A reflective type with four 0.5" seven-segment characters. LCD's require excitation of each segment and a common backplane with a 30-100 Hz square wave alternating between 0 and 5 volts. A segment that is to be "on" is fed a signal 180° out of phase with the backplane excitation, so that the net field across it varies from +5V to -5V. An "off" segment is excited in phase with the backplane. A Siliconix DF411 four-digit LCD decoder-driver was used to provide the proper AC excitation to the display. This chip had four BCD data input lines, plus four digit-select inputs to select which of the four internal seven-segment output latches were to receive the decoded result of the input data.

The twelve bits of digital data required as an input by the D/A converter were sent to the converter in three





four-bit words because of the limited number of I/O ports available. These words were held by three four-bit latches (IC37-39), each of which was enabled separately by the appropriate output of the enable decoder. This arrangement saved using a second 6530 I/O chip to provide the 12 bits in parallel, but made the successive-approximation A/D. software somewhat more complex.



## V. SYSTEM SOFTWARE

### A. STRUCTURE AND GENERAL FEATURES

The software which this instrument used to perform its basic functions, not including video displays or weight loss corrections, required approximately 1450 bytes. It was organized into a main operating program, seven subroutines, two interrupt service routines, a power-up routine, and nine minor programs. Each of these was written in the 6800 mnemonic assembly language and was compiled and debugged separately on a Tektronix 8002 microprocessor development system (MDS). Reference 12 was used extensively in developing the software. A listing of the programs is provided at the end of this report.

Each of the 16 keys on the input keyboard commanded the instrument to take a particular action or display a particular piece of data, as shown in Table VII. Three of these actions were not yet implemented at the time this report was written. Of the remaining 13 keys, two called the main operating program (with different input data), one was a "stop" key, one called the "zero-memory" subroutine, and each of the other nine called a different minor program. In general, functions which were used in several different operating modes of the system, such as averaging, A/D conversion, and hex-to-BCD conversion, were implemented as subroutines. Only one of these was used directly as a response to a



key input. Key response was accomplished with individual programs, some of which did little more than set up data for a subroutine, then call it. These programs could actually be thought of as subroutines themselves, since each ended with an unconditional jump back to the keyboard input routine.

TABLE VII

FUNCTIONS OF INPUT KEYS

Programs Whose Names are in Parentheses not yet Written

| Key | Program Called | Function                             |
|-----|----------------|--------------------------------------|
| 0   | KEYIN          | Stop program in progress and wait    |
| 1   | OPER           | Start an engine test, no temperature |
| 2   | OPER           | Start test, measuring temperature    |
| 3   | CALSET         | Set up for calibration               |
| 4   | CALIB          | Accept calibration                   |
| 5   | DDTHST         | Display one thrust A/D output        |
| 6   | DDTEMP         | Display one temperature A/D output   |
| 7   | DTHST          | Display peak thrust to 0.1N          |
| 8   | DIMP           | Display total impulse to 0.01N-sec   |
| 9   | DBTIM          | Display burn time to 0.01 sec        |
| A   | (DTV)          | Display thrust curve on TV           |
| B   | DTEMP          | Display peak temperature to 1°C      |
| C   | (APCOR)        | Apply weight-loss correction         |
| D   | (DOSC)         | Display thrust curve on oscilloscope |
| E   | DDTIM          | Display delay time to 0.01 sec       |
| F   | ZERO           | Clear all RAM                        |



When power is applied to a 6802 microprocessor and the proper timing is followed on its RESET pin, the chip goes to address locations FFFE and FFFF for its startup routine vector. This vector is simply the address of the first step of the power-up program routine. This routine, entitled PWRUP in this system, must start with a CLI (clear interrupt flag) command and should set the initial value of the stack pointer. In this system, it also temporarily disabled timer interrupts, set the data direction registers (PAD and PBD) of the 6530 for input or output as appropriate, and cleared all static and dynamic RAM. Dynamic memory requires an initial clearing or refresh before it can be used after power is first applied to it. The PWRUP routine turned on the CLEAR LED as its last step (leaving the other LED's off), indicating that the RAM was clear of all test data. The system then entered a loop where it waited for a keyboard input.

Depressing any key on the instrument keyboard caused an IRQ interrupt to be sent to the 6802. In response, the 6802 went to addresses FFF8 - FFF9 and found the vector for the IRQ service routine, which was entitled IRQRES. This routine began with a one-millisecond wait loop to give the key switch "ringing" time to damp out. It then stored the four 6530 input bits PBI - PB5 which contained the output from the keyboard encoder in memory location 0046. If the key input was the stop command (key 0) or the zero-memory command (key F), the routine forced an immediate return to the KEYIN





keyboard response routine to do this and terminated any other action that the instrument had been doing. Otherwise, IRQRES simply returned the system to whatever it was doing before the interrupt, and the new mode action was not taken until the next time the system returned normally to KEYIN.

The KEYIN routine used an action pointer table technique [Ref. 12] to develop responses to the key input commands. This routine compared the contents of address 0046 (filled by IRQRES) to those of address 0049, the last command executed by the system. If they were the same, it did nothing. This meant that in order to repeat a particular key action, some other key (generally the "stop" key, key 0) had to be used in between. If the two memory location contents were different, indicating that an unexecuted command was pending, then the key command (multiplied by 3) was used as an offset for an indexed-address jump into an action pointer table entitled VECTOR, which started at address FC00. This table contained unconditional jump instructions, directing the system to the appropriate programs for response to each key. For example, if key 5 was pressed, the system jumped to address  $FC00 + (3 \times 5) = FC0F$ , where it found the command JMP FBA0 telling it to jump unconditionally to FBA0, the starting address of the program responding to that key.

The accuracy of the time-based measurements made by this instrument (burn and delay times and total impulse) depended on having an accurate timing reference available to trigger an A/D conversion exactly every two milliseconds.



The easiest way to do this was to use the 6530 programmable timer to generate a non-maskable interrupt to the 6802 at this interval. The NMI interrupt sent the 6802 to addresses FFFC-FFFD, where it found the vector sending it to the response routine for this interrupt, NMIRES. This routine began by reloading the counter so that another interrupt would be generated in 2.00 milliseconds. It then enabled the RAM refresh input to the 3242 dynamic RAM controller for 128 microseconds, giving it time to automatically generate all the signals necessary for a refresh cycle. If a mode was being executed which required A/D conversion (keys 1 through 6), the program jumped to the ADC12 A/D conversion subroutine before returning from the interrupt. Otherwise it returned from interrupt directly at this point.

Because this system had only 48 bytes of RAM available for stack and these bytes were located just above important program memory, considerable care was taken to ensure that the stack did not overflow. The 6802 uses seven bytes of stack in responding to an interrupt and three bytes to jump to a subroutine, so this limited the depth to which subroutines could be nested, particularly in the interrupt service routines. Several early versions of this system's software overflowed the stack. Such overflows were not possible with the final design.

Although many sections of this system's software were debugged individually on the Tektronix MDS, several of the major interactions between them were not. These interactions



were the ones which depended on the occurrence of NMI timer interrupts and real-time thrust inputs. MDS emulation provides line-by-line traceouts of the status of every CPU register as each program instruction is executed, but to provide this and other valuable debugging services it must slow the execution speed by a large factor. Interrupt inputs to the MDS are enabled for only a small fraction of each instruction execution cycle, so the MDS seldom sees the negative-going edge it requires to sense an NMI interrupt. This meant that the real-time NMI-dependent processes of the system could not be emulated. A vast amount of time was required to debug these subroutines and interrupt interactions using a Paratronics 532 Logic State Analyzer. This device permitted real-time operation of the system with its own CPU in place, rather than the emulator plug required by the MDS, but it provided access only to the contents of the external pins of the CPU (address and data bus) and not to internal registers. It allowed no interaction for modifying the contents of memory, and could provide only 256 clock cycles of traceout at once.

#### B. SOFTWARE A/D CONVERSION

The hardware required to accomplish a 12-bit successive-approximation A/D conversion using software and a D/A converter has been described previously. The function of the software was to generate the proper 12 bits of data to send to the converter, working with one four-bit word at a time



while leaving the other eight bits unchanged. The software also generated control signals for the sample-and-hold circuit and packed the A/D conversion output from the last four bits of three separate bytes into one and a half consecutive bytes.

All of the A/D software was contained in one subroutine entitled ADC12, which occupied 131 bytes and required 715 microseconds to perform a conversion. This program operated in straight binary, converting the digital test values to the complementary binary required by the DAC before sending them out, then changing the final result back to the straight binary used in the rest of the system. ADC12 could be called repeatedly only by the NMIRES interrupt response program, so the timer NMI interrupt had to be enabled by any program which required more than one A/D conversion. These programs generally used a WAI (wait for interrupt) command where the A/D data was required so that their execution was stopped at this point until the data was available from ADC12 after the next timer interrupt.

The ADC12 subroutine began by sending a "sample" command to the SHC for 14 microseconds, then a "hold" command. Next it set the initial digital signal to the DAC to 01111..., corresponding to a 0.00V analog output since the DAC operated over a -5V to +5V output range. It then entered a loop where it worked on only one four-bit word (starting with the most significant four bits), leaving the other two words set at





their initial values. Straight binary will be used hereafter to describe the functioning of this program.

The ADC12 program set the initial value of the current four-bit test word to 1000, and set a rotating-bit word to 0100. It sent the initial test word to the appropriate latched DAC input by adding the necessary final three bits (PA2 - PA0) to enable the proper latch. After 45 microseconds of executing other instructions, it examined the output of whichever comparator had been enabled by the program which had called ADC12. An output of "1" indicated that the DAC analog output was less than the signal being converted. In this case, the rotating bit was ORed to the test word, increasing its analog equivalent voltage. If the comparator output was "0", the rotating bit was subtracted from the test word instead. In either case, the rotating bit was then shifted one position to the right and another conversion cycle was started. After every fourth cycle, a new word was begun.

The branches possible in a four-bit straight binary successive-approximation A/D conversion are illustrated in Figure 5.

#### C. MAIN OPERATING PROGRAM

The main operating program of this instrument, entitled OPER, was the program used during an engine static test. Its function was to recognize the occurrence of such events as start of thrust, thrust termination, and gas-generation






Figure 5. Four-bit straight-binary successive approximation A/D conversion. Upper branches taken when comparator output is 0.



charge actuation regardless of the shape of the input thrust variation. It computed the value of burn and delay times and peak thrust and added thrust outputs to accumulate total impulse, all based strictly upon the input values it received every two milliseconds from the ADC12 subroutine. Depending on whether it was called by depressing input key 1 or key 2, it either ignored the temperature peak detector or accepted its output once at the end of a test, respectively. This program was 365 bytes in length. Its operating time varied widely during the course of a single engine test because of its numerous conditional branching instructions, but it was always short enough that its operation (including an A/D conversion) was completed in the two-millisecond interval between NMI timer interrupts.

The flow diagram for OPER is shown in Figure 6. The first action of the program was to check memory location 004E to see if a calibration had been performed since the system had been turned on. A calibration, which used the CALSET and CALIB routines described in the next section of this chapter, caused a flag value to be placed in this memory location. Only if a calibration had been performed would the program permit initiation of a test. It indicated that a test was in progress by turning off the CLEAR LED and turning on the TEST LED. It then enabled the thrust comparator for the A/D conversion, and averaged the result of eight conversions to obtain a value of thrust transducer output corresponding to zero thrust input. This feature






Figure 6. Flowchart of main operating program.








Figure 6. (Continued)






Figure 6. (Continued)



eliminated the need to carefully trim the transducer analog output to -5.000 V before each test, since throughout the rest of the program this zero value was subtracted from the A/D output to obtain the actual net thrust.

After the preliminary preparations for a test were completed, the OPER routine waited for a thrust input of 0.50 N or greater lasting at least three timer periods (0.006 seconds) before it decided that a valid test had begun. Setting a threshold in this manner prevented a single large noise spike before engine ignition from erroneously causing the program to begin accumulating durations and total impulse. The time at which this threshold was satisfied was declared by the program to be time zero for computing durations, and for the next 9.50 seconds or until it decided engine burnout had occurred (whichever came first) it accumulated thrust outputs for total impulse and examined them to detect a valid peak value.

The peak value detection logic rejected any peaks which occurred more than 0.20 seconds after a previous peak of 4.5 Newtons or greater, but accepted all others. "Peaks" rejected by this criterion were almost always just spurious output spikes, caused by ejection of an engine casing by its gas generation charge when there was no delay between burnout and actuation of this charge. The most recent valid value of peak thrust was placed in addresses 002C and 002D during each cycle of OPER until burnout, at which time the updating was stopped.



During each cycle of the program between the times when it recognized ignition and burnout, the net thrust was added to a three-byte memory location where total impulse was accumulated. The design limit of this system was 99.99 N-sec. of total impulse. Since 99.99 Newtons was 3150 A/D counts and one second was 500 A/D cycles, the maximum value which this accumulation could reach was  $500 \times 3150 = 1.575 \times 10^6$ , or 21 bits. The net thrust was obtained by sending the ADC12 direct output to the NETTST subroutine, where the zero reference value was subtracted.

The burnout detection logic defined burnout as that moment when the thrust output of an engine first dropped below 1/16 of the peak value recorded by that engine. This is a more flexible criterion than the fixed threshold value used to define ignition. At the moment when burnout was recognized, the total impulse value accumulated was sent to the DIMP subprogram to be converted to a value in N-sec. and then to be displayed. The value of the A/D conversion cycle counter was also sent to a memory location to be remembered as the burn time.

After burnout was sensed, the program waited for the occurrence of a thrust spike at least 0.50 N greater than the threshold used to determine the burnout. This was presumed to have come from the activation of the gas-generation charge on the engine, and its time of occurrence minus the burn time of the engine was stored as the delay time. At this point, if the without-temperature mode of OPER was the





one in progress, the test was considered to be terminated and the TEST LED was turned off.

If the with-temperature mode was in progress, or if no post-burnout thrust spike occurred, OPER continued until 73 seconds after engine ignition before terminating. Temperature data, if required, was taken just before termination by averaging eight samples of the output of the peak detector circuit. This data was then converted to degrees Centigrade and displayed on the LCD by the DTEMP subprogram.

After each test the peak thrust, burn time, delay time, total impulse, and (if used) peak temperature were available for display on the LCD by pressing the appropriate input key. The instrument could then be prepared for a new test by using key F to clear all RAM locations except those five where the calibration data was stored. Doing this caused the CLEAR LED to come back on and left the CALIBRATED LED on.

#### D. SUBROUTINES AND MINOR PROGRAMS

Up to this point only the two principal programs used by this system, plus the interrupt response and power-up routines and a few subroutines, have been described. The remaining subroutines and minor subprograms were either quite straightforward or very short and will be discussed only briefly.

The CALSET subprogram was entered in response to key 3. It enabled the NMI interrupt in order to gain access to the A/D subroutine, then averaged eight A/D outputs using the



AVG8 subroutine. This result was used as the zero-thrust reference value in the CALIB subprogram.

The CALIB subprogram was entered in response to key 4, and was meant to be preceded by CALSET. Before selecting this routine, but after executing CALSET, a 10.00 Newton calibration weight was placed on the thrust transducer. CALIB then averaged eight A/D outputs using AVG8 and subtracted from this result the zero-thrust reference value developed in CALSET. The difference was the net output for 10.00 N of thrust/weight. This calibration value was stored in a section of RAM that was not erased between static tests, and was used to convert A/D outputs from the operating program into units of thrust or impulse. Upon completion of CALIB, the CALIBRATED LED was turned on.

The HEXBCD subroutine accepted two bytes of hexadecimal data as an input and, using the binary-to-BCD conversion algorithm developed in Ref. 12, converted this data to a four-digit BCD result. The total impulse display program (DIMP) could conceivably generate a hex quantity which would overflow four BCD digits, so HEXBCD included a provision to generate an output of 9999 if too large a hex input were provided. It put the BCD output in the high four bits of four data words, then added the proper data routing control bits to the end of each word to send it to the appropriate LCD digit.

The DTHST subprogram was entered in response to key 7. It took the peak thrust A/D hex value developed by the



operating program during a static test and multiplied it by 100 with the MULT subroutine, then divided it by the calibration value with the DVID subroutine. The result was the hex value of peak thrust in tenths of Newtons. This was then displayed using HEXBCD.

The DTEMP subprogram was entered in response to key B. It divided the 12-bit A/D count resulting from conversion of the peak detector output during a test by approximately 8. This made each bit of what remained equal to one degree C., so the quotient was converted by HEXBCD and displayed.

The DIMP subprogram was entered in response to key 8. It started by doubling the hex value accumulated by the operating program in the three-byte total impulse memory. This converted the value to units of bit-milliseconds. This was divided by the calibration, which had units of bits per 10 N, putting the quotient in units of 0.01 N-sec. This was sent to HEXBCD for conversion and display.

The DBTIM (key 9) and DDTIM (key E) subprograms were combined since their function was virtually identical. They converted the burn time and delay time, respectively, that had been accumulated by the operating program into units of 0.01 second and sent them to HEXBCD. This conversion was accomplished by dividing five into the respective counts of NMI interrupts, which had been incremented by OPER every 0.002 second.

The DDTHST (key 5) and DDTEMP (key 6) subprograms were also so similar that they were combined. They provided an



LCD output of the direct, unconverted result of one A/D conversion of the thrust and temperature transducer outputs, respectively. These programs simply enabled the appropriate comparator, called the ADC12 subroutine once, then sent the result to HEXBCD.

The MULT and DVID subroutines provided 16 x 24-bit integer multiplication and 24/24-bit integer division, respectively, for use throughout the program. Both used standard algorithms taken from Ref. 12. Considerable care was taken to set up the arithmetic operations required by this system so that they could be performed in integer arithmetic rather than floating-point.





## VI. CONCLUSION

The objective of this project was to develop a microprocessor-based instrument for accurate static-test measurement of five performance parameters of small solid-fuel rocket engines. Maximum and minimum design values for these parameters and maximum allowable errors were established to define the performance required from the system. It was then designed and built with the additional constraints that it have minimum parts cost and that it must operate from two 12-volt batteries and draw no more than one ampere from either. The final design drew 0.69 ampere from +12V and 0.18 ampere from -12V, and had a 1979 parts cost of about \$350.

In the process of building this instrument and debugging its 1450 bytes of software, it became apparent that major simplifications of the software could have been achieved by using slightly more expensive and sophisticated parts. Nevertheless, the system was eventually made to operate exactly as desired, displaying the values of the five parameters one at a time on a four-digit liquid crystal display after each static test.

A wide variety of solid-fuel model rocket motors were static tested to verify the instrument's performance. Every feature of the system functioned as designed on every test.



Static calibrations proved that the system thrust and temperature transducers and its A/D conversion routine delivered satisfactory static accuracy. There is no such thing as a precision rocket engine which could be used as a realistic dynamic reference source, so the real-time accuracy could only be checked approximately. This was done by recording the analog transducer output signals on a chart recorder during a static test and measuring them to estimate the values of the five parameters. These values were in excellent agreement with the values then presented by the system on its LCD.

The instrument developed in this project made extensive use of the arithmetic and decision-making capabilities of a microprocessor to deliver accurate measurements with relatively inexpensive hardware requiring minimal adjustment by the operator. These measurements were accurate regardless of the shape of the input signal as long as this signal was within the design limits of the system.

This instrument may be modified to test engines of up to 1000 Newtons of peak thrust and 1000 Newton-seconds of total impulse by replacing resistor R in the thrust amplifier circuit (Figure 7) by a 2000 ohm resistor and by replacing the 10.0 N calibration weight with a 100 N weight. In this case, the thrust data output will be in whole Newtons and the impulse data in tenths of Newton-seconds. This will degrade the accuracy for tests of small engines.



# APPENDIX A. CIRCUIT SCHEMATICS




Figure 7. Thrust transducer amplifier and filter circuit.






Figure 8. Thermocouple amplifier and filter circuit.








Figure 9. Thermocouple compensation and peak detection circuit.






Figure 10. Digital interface circuit.






Figure 11. Microprocessor and its support circuitry.






Figure 12. Memory system.









## APPENDIX B. INSTRUMENT OPERATING INSTRUCTIONS

1. Apply external +12V and -12V power to the system.
2. Turn on the switch to provide internal +5V power to the digital circuits. The CLEAR LED should come on and the LCD should read 0000.
3. Trim the BRIDGE NULL potentiometer while monitoring thrust transducer output voltage until this voltage is slightly above -5.00 V.
4. Place the temperature sensor in an ice bath and trim the TEMP NULL potentiometer while monitoring temperature transducer output voltage until this voltage is -0.400 V.
5. Place the thrust transducer flat and press key 3 to set up for calibration.
6. With the thrust transducer still flat, place the 10.0 N calibration weight in the engine holder, wait a few seconds, and press key 4. The CALIBRATED LED should come on.
7. Place the thrust transducer on its side and clamp it securely to an extremely rigid and sturdy support.
8. Place the engine to be tested in the engine holder. Ensure that the ignition leads exert no force on the engine along its thrust axis. Zero the peak detector circuit. Attach temperature sensor to the engine.



9. Press key 1 or key 2 to initiate a test. The TEST LED should come on and the CLEAR LED should go out. Press key Ø if it is necessary to cancel a test before the engine is fired.
10. Fire the engine. The measured total impulse should appear on the LCD at burnout.
11. When the TEST LED goes out, indicating the end of the test, read out the performance parameters of interest by pressing keys 7, 8, 9, B, and/or E.
12. Clear the memory to set up for a new test by pressing key F. The CLEAR LED should come on and the CALIBRATED LED should remain on. Return to step 8 to conduct a new test.



# COMPUTER PROGRAM

```

      FI00      >  ORG      2F100H
FI00 CE0003    ADC12  LEX      #03
FI03 8602      LDA A     #02      ;SET MUX WORD CONTROL
FI05 971C      STA A     1CH
FD07 86F8      LDA A     #0F8H
FI09 B71340    STA A     PAI      ;SEND "SAMPLE" TO SHC
FD0C 86F9      LLA A     #0F8H
FI0E B71340    STA A     PAI      ;SET LOW 11 DAC BITS TO '1'
FD11 8672      LDA A     #272H
FI13 B71340    STA A     PAI      ;SEND "HOLD" TO SHC
FI16 8640      WNEX  LLA A     #40H      ;BEGIN NEW WORD A/D
FI18 971C      STA A     11H      ;SET ROTATING BIT
FD1A 8605      LDA A     #05
FD1C 971B      STA A     1BH      ;SET BIT COUNTER
FI1E 8680      LLA A     #80H      ;SET DAC INITIAL VALUE
FD20 2026      BRA      BAKER
FI22 961E      START LLA A     1EH      ;BEGIN NEW BIT A/D
FD24 8001      SUB A     #01      ;DECREMENT BIT COUNTER
FI26 971B      STA A     1EH
FD28 272B      BEQ      NEXT      ;GO TO NEXT WORD AFTER 4 BITS
FI2A 01        NOP
FI2B B61342    LDA A     PBD
FD2E B61342    LDA A     FBD
FI31 01        NOP
FI32 01        NOP
FD33 8401      AND A     #01      ;EXAMINE COMPARATOR
FI35 260A      BNE      PAST      ;BRANCH IF SAMPLE > DAC
FD37 961E      LDA A     1EH
FI39 1611      LLA B     11H
FI3B 10        SBA      ;SUBTRACT ROT BIT FROM TEST
FD3C 74001D    LSR      11H      ;SHIFT ROTATING BIT
FI3F 2007      BRA      BAKER
FD41 961E      PAST  LDA A     1EH
FI43 9A11      ORA A     11H      ;OR ROT BIT TO TEST
FI45 74001D    LSR      11H      ;SHIFT ROTATING BIT
FI48 84F0      BAKER ANL A     #CF0H ;MASK OFF LAST 4 BITS
FD4A 971E      STA A     1EE
FI4C 88F0      EOR A     #0F0H      ;COMPLEMENT OUTPUT TO DAC
FI4E 9A1C      ORA A     1CH      ;ADD MUX CONTROL
FI50 B71340    STA A     PAI      ;SEND TO DAC
FI53 20C1      BRA      START
FD55 961E      NEXT  LDA A     1EH
FI57 A71F      STA A     1FH.X      ;STORE ADC VALUE UNPACKED
FI59 7A001C    DEC      1CH      ;AND UNCOMPLEMENTED
FI5C 09        LEX
FI5L 2EB7      BGT      WNEX      ;GO TO NEXT WORD
FI5F 9623      LLA A     20H      ;PACK ADC VALUE IN 2 BYTES
FI61 CE0004    LDX      #04
FI64 44        PACK  LSR A
FD65 09        LEX
FD66 26FC      BNE      PACK
FI68 9A21      ORA A     21H
FI6A 9724      STA A     24H      ;LOW ADC BYTE

```





|             |       |       |        |                          |
|-------------|-------|-------|--------|--------------------------|
| FD6C 9622   |       | LIA A | 22H    |                          |
| FD6E C50004 |       | LIX   | #04    |                          |
| FD71 44     | PACK2 | LSR A |        |                          |
| FD72 09     |       | LEX   |        |                          |
| FD73 26FC   |       | BNE   | PACK2  |                          |
| FD75 9725   |       | STA A | 25H    | ;HIGH ADC BYTE           |
| FD77 86FC   |       | LDA A | #0FCH  |                          |
| FD79 9024   |       | SUB A | 24H    |                          |
| FD7B 9724   |       | STA A | 24H    |                          |
| FD7D 860F   |       | LIA A | #0FH   |                          |
| FD7F 9225   |       | SBC A | 25H    |                          |
| FD81 9725   |       | STA A | 25H    | ;CHANGE SIGN OF RESULT   |
| FD83 39     |       | RTS   |        |                          |
| FC37        |       | ORG   | 0FC37H |                          |
| FC37 8C09   | AVG8  | LDA A | #09    | ;AVERAGES 8 A/D OUTPUTS  |
| FC39 9716   |       | STA A | 16H    |                          |
| FC3B 8600   |       | LDA A | #00    |                          |
| FC3D 9714   |       | STA A | 14H    |                          |
| FC3F 9715   |       | STA A | 15H    |                          |
| FC41 9616   | AVG   | LEA A | 16H    |                          |
| FC43 8001   |       | SUB A | #1     |                          |
| FC45 9716   |       | STA A | 16H    |                          |
| FC47 2F12   |       | BLE   | RUN1   |                          |
| FC49 01     | WAIT  | NOP   |        | ;WAIT FOR A/D OUTPUT     |
| FC4A 01     |       | NOP   |        |                          |
| FC4B 3E     |       | WAI   |        |                          |
| FC4C 9614   |       | LIA A | 14H    |                          |
| FC4E D624   |       | LDA B | 24H    |                          |
| FC50 1B     |       | ABA   |        |                          |
| FC51 9714   |       | STA A | 14H    |                          |
| FC53 9615   |       | LDA A | 15H    |                          |
| FC55 9925   |       | ADC A | 25H    |                          |
| FC57 9715   |       | STA A | 15H    | ;ADD 8 A/D OUTPUTS       |
| FC59 2036   |       | BRA   | AVG    |                          |
| FC5B C50003 | RUN1  | LIX   | #03    |                          |
| FC5E 740015 | RUN   | LSR   | 15H    |                          |
| FC61 760014 |       | ROR   | 14H    |                          |
| FC64 09     |       | DEX   |        | ;DIVIDE SUM BY 8 FOR AVG |
| FC65 26F7   |       | BNE   | RUN    |                          |
| FC67 39     |       | RTS   |        |                          |
| 1340        | PAL   | EQU   | 1340H  |                          |
| 1342        | PBL   | EQU   | 1342H  |                          |
|             |       | END   |        |                          |



|             |       |   |       |        |                                   |
|-------------|-------|---|-------|--------|-----------------------------------|
| FE00        | FE00  | > | ORG   | 0FE00H |                                   |
| FE00 964E   |       |   | LIA A | 4EH    |                                   |
| FE02 910F   |       |   | CMP A | #2FH   |                                   |
| FE04 26FA   |       |   | BNE   | OPER   | ;DO NOT PROCEED IF UNCALIBRATED   |
| FE06 3F     |       |   | SWI   |        |                                   |
| FE07 8602   |       |   | LIA A | #2     |                                   |
| FE09 9726   |       |   | STA A | 26H    | ;SET INTERVAL COUNTER             |
| FE0B 8620   |       |   | LDA A | #20H   |                                   |
| FE0D 9729   |       |   | STA A | 29H    | ;SET MEMORY POINTER               |
| FE0F 86D3   |       |   | LDA A | #0D3H  |                                   |
| FE11 B71340 |       |   | STA A | PAL    | ;ENABLE THRUST COMPARATOR         |
| FE14 8663   |       |   | LDA A | #63H   |                                   |
| FE16 F71340 |       |   | STA A | PAL    | ;SET UP LED                       |
| FE19 9742   |       |   | STA A | 42H    |                                   |
| FE1B B1FC37 |       |   | JSR   | AVG8   | ;AVG PRESENT OUTPUT FOR ZERO REF  |
| FE1E 3E     | STRT  |   | WAI   |        | ;WAIT FOR TIMER INTERRUPT         |
| FE1F B1F828 |       |   | JSR   | NETTST | ;SUBTRACT ZERO REF FROM A/D       |
| FE22 9648   |       |   | LIA A | 48H    |                                   |
| FE24 260F   |       |   | BNE   | STRT1  | ;BRANCH IF THST STARTED           |
| FE26 9617   |       |   | LIA A | 17H    |                                   |
| FE28 8612   |       |   | SUB A | #18    |                                   |
| FE2A 9618   |       |   | LIA A | 18H    |                                   |
| FE2C 8200   |       |   | SEC A | #0     |                                   |
| FE2E 21E3   |       |   | BLT   | STRT   | ;WAIT FOR THRUST > 0.50N          |
| FE30 7A0026 |       |   | IFC   | 26H    |                                   |
| FE33 20E9   |       |   | BGE   | STRT   | ;WAIT FOR THST HI FOR 3 COUNTS    |
| FE35 8601   | STRT1 |   | LIA A | #1     |                                   |
| FE37 9748   |       |   | STA A | 48H    |                                   |
| FE39 9B27   |       |   | ADD A | 27H    |                                   |
| FE3B 9727   |       |   | STA A | 27H    | ;TIME COUNTER LOW BYTE            |
| FE3D 9628   |       |   | LDA A | 28H    |                                   |
| FE3F 8900   |       |   | ADC A | #0     |                                   |
| FE41 9728   |       |   | STA A | 28H    | ;TIME COUNTER HIGH BYTE           |
| FE43 818F   |       |   | CMP A | #8FH   |                                   |
| FE45 2607   |       |   | BNE   | TEST1  |                                   |
| FE47 8602   |       |   | LIA A | #02    |                                   |
| FE49 9739   |       |   | STA A | 39H    |                                   |
| FE4B 7EFF20 | >     |   | JMP   | DELAY  | ;STOP TIMING AFTER 73 SEC         |
| FE4E 962B   | TEST1 |   | LIA A | 2BH    |                                   |
| FE50 2703   |       |   | BEQ   | TEST   |                                   |
| FE52 7EFF17 | >     |   | JMP   | TEST3  | ;BYPASS IF BURNOUT PAST           |
| FE55 9627   | TEST  |   | LDA A | 27H    |                                   |
| FE57 808E   |       |   | SUB A | #8EH   |                                   |
| FE59 9626   |       |   | LIA A | 26H    |                                   |
| FE5B 8212   |       |   | SEC A | #12H   |                                   |
| FE5D 2104   |       |   | BLT   | BURN   | ;STOP STORING THST AFTER 9.92 SEC |
| FE5F 8601   |       |   | LIA A | #01    |                                   |
| FE61 972B   |       |   | STA A | 2BH    |                                   |
| FE63 962B   | BURN  |   | LIA A | 2BH    |                                   |
| FE65 2703   |       |   | BEQ   | STORE  |                                   |
| FE67 7EFF25 | >     |   | JMP   | TEST2  | ;BYPASS IF BURNOUT FAST           |
| FE6A 8603   | STORE |   | LDA A | #3     |                                   |
| FE6C 9B2A   |       |   | ADL A | 2AH    | ;MEMORY POINTER LOW               |
| FE6E 972A   |       |   | STA A | 2AH    |                                   |
| FE70 9629   |       |   | LDA A | 29H    |                                   |
| FE72 8900   |       |   | ADC A | #0     | ;MEMORY POINTER HIGH              |
| FE74 9729   |       |   | STA A | 29H    | ;INCREMENT MEMORY POINTER BY 1    |
| FE76 1E29   |       |   | LDX   | 29H    | ;PUT MEMORY POINTER IN X          |
| FE78 9620   | STOR1 |   | LIA A | 20H    |                                   |
| FE7A A700   |       |   | STA A | X      |                                   |
| FE7C 09     |       |   | DEX   |        |                                   |
| FE7D 9621   |       |   | LLA A | 21H    |                                   |
| FE7F A700   |       |   | STA A | X      |                                   |



|               |        |       |        |                                    |
|---------------|--------|-------|--------|------------------------------------|
| FE81 09       |        | DEX   |        |                                    |
| FE82 9622     |        | LDA A | 22H    |                                    |
| FE84 A720     |        | STA A | X      |                                    |
| FE86 9617     | FMAX   | LDA A | 17H    |                                    |
| FE88 9021     |        | SUB A | 21H    | ;SUBTRACT FMAX FROM THRUST         |
| FE8A 9618     |        | LDA A | 18H    |                                    |
| FE8C 922C     |        | SEC A | 2CH    |                                    |
| FE8E 2132     |        | BLT   | IMPULS | ;BRANCH IF FMAX > THRUST           |
| FE90 9621     |        | LLA A | 21H    |                                    |
| FE92 C087     |        | SUB B | #135   | ;WAS PREVIOUS FMAX > 4.5N?         |
| FE94 D62C     |        | LDA B | 2CH    |                                    |
| FE96 C200     |        | SEC B | #00    |                                    |
| FE98 2C12     |        | BGE   | TIMT   | ;BRANCH IF YES                     |
| FE9A 9617     | NEWMAX | LDA A | 17H    |                                    |
| FE9C 9721     |        | STA A | 21H    |                                    |
| FE9E 9618     |        | LDA A | 18H    |                                    |
| FEA0 972C     |        | STA A | 2CH    | ;SET FMAX = THRUST                 |
| FEA2 9627     |        | LDA A | 27H    |                                    |
| FEA4 972E     |        | STA A | 2EH    |                                    |
| FEA6 9628     |        | LDA A | 28H    |                                    |
| FEA8 972F     |        | STA A | 2FH    | ;REMEMBER TIME OF FMAX             |
| FEAA 2016     |        | BRA   | IMPULS |                                    |
| FEAC 9627     | TIMT   | LDA A | 27H    |                                    |
| FEAE 902E     |        | SUB A | 2EH    |                                    |
| FEB0 9730     |        | STA A | 30H    |                                    |
| FEB2 9628     |        | LDA A | 28H    |                                    |
| FEB4 922F     |        | SBC A | 2FH    |                                    |
| FEB6 9731     |        | STA A | 31H    | ;FIND TIME-TMAX                    |
| FEB8 9630     |        | LDA A | 30H    |                                    |
| FEBA 8064     |        | SUB A | #100   |                                    |
| FEBC 9631     |        | LDA A | 31H    |                                    |
| FEBE 8203     |        | SEC A | #00    | ;LAST FMAX MORE THAN 2.2 SEC PAST? |
| FEC0 2115     |        | BLT   | NEWMAX | ;BRANCH IF NO                      |
| FEC2 9632     | IMPULS | LLA A | 32H    | ;ADD THST TO TOTAL IMPULSE         |
| FEC4 9B17     |        | ADD A | 17H    |                                    |
| FEC6 9732     |        | STA A | 32H    |                                    |
| FEC8 9633     |        | LDA A | 33H    |                                    |
| FECA 9918     |        | ADC A | 18H    |                                    |
| FECC 9733     |        | STA A | 33H    |                                    |
| FECE 9634     |        | LDA A | 34H    |                                    |
| FED0 8900     |        | ADC A | #00    |                                    |
| FED2 9734     |        | STA A | 34H    | ;TOTAL IMPULSE HIGH BYTE           |
| FED4 962C     |        | LLA A | 2CH    | ;DIVIDE FMAX BY 16                 |
| FED6 D621     |        | LLA B | 21H    |                                    |
| FED8 C00004   |        | LDX   | #04    |                                    |
| FEDB 44       | DIVBY  | LSR A |        |                                    |
| FEDC 56       |        | ROR B |        |                                    |
| FEDD 09       |        | DEX   |        |                                    |
| FEDE 26FB     |        | BNE   | DIVBY  |                                    |
| FEE0 C900     |        | ADC B | #00    |                                    |
| FEE2 D735     |        | STA B | 35H    | ;LSD OF FMAX/16                    |
| FEE4 8900     |        | ADC A | #00    |                                    |
| FEE6 9736     |        | STA A | 36H    | ;MSD OF FMAX/16                    |
| FEE8 9635     |        | LDA A | 36H    |                                    |
| FEEA 1017     |        | SUB B | 17H    |                                    |
| FEEC 1C36     |        | LLA B | 36H    |                                    |
| FEED 1214     |        | SBC B | 1EH    | ;FMAX/16 - THST                    |
| FEF0 2C03     |        | BGE   | TEST2  | ;BRANCH IF THST < FMAX/16          |
| FEF2 7EF11E > |        | JMP   | STRT   |                                    |
| FEF5 9621     | TEST2  | LLA A | 2BH    |                                    |
| FEF7 2615     |        | BNE   | TEST3  | ;BRANCH IF BURNOUT PAST            |
| FEF9 9627     |        | LDA A | 27H    |                                    |
| FEFB 8064     |        | SUB A | #100   |                                    |



|             |        |       |         |                                |
|-------------|--------|-------|---------|--------------------------------|
| FEFD 9628   |        | LDA A | 28H     |                                |
| FEFF 8200   |        | SBC A | #C0     | ;IS TIME > 0.20 SEC?           |
| FF01 2C03   |        | BGE   | TBURN   | ;BRANCH IF YES                 |
| FF03 7EFE1E | >      | JMP   | STRT    | ;WAIT FOR NEXT A/D OUTPUT      |
| FF06 8601   | TBURN  | LDA A | #01     |                                |
| FF08 972E   |        | STA A | 2FH     |                                |
| FF0A 9627   |        | LDA A | 27H     |                                |
| FF0C 9737   |        | STA A | 37H     | ;BURN TIME LOW BYTE            |
| FF0E 9626   |        | LDA A | 26H     |                                |
| FF10 9738   |        | STA A | 38H     | ;BURN TIME HIGH BYTE           |
| FF12 7EFEC8 |        | JMP   | LIMP    |                                |
| FF15 2012   |        | BRA   | GOBCK   |                                |
| FF17 9635   | TEST3  | LDA A | 35H     |                                |
| FF19 8E0F   |        | ALD A | #15     |                                |
| FF1B 9636   |        | LDA A | 36H     |                                |
| FF1D 8900   |        | ADC A | #00     |                                |
| FF1F 9635   |        | LDA A | 35H     |                                |
| FF21 9017   |        | SUB A | 17H     |                                |
| FF23 9636   |        | LDA A | 36H     |                                |
| FF25 9218   |        | SBC A | 18H     | ;IFMAX/16)-0.5N - THST         |
| FF27 2E03   |        | BLT   | DELAY   | ;BRANCH IF EJECTION OCCURS     |
| FF29 7EFL1E | >      | JMP   | STRT    |                                |
| FF2C 9639   | GOBCK  | LIA A | 39H     |                                |
| FF2E 2610   | DELAY  | BNE   | TEMP1   | ;BRANCH IF EJECTION PAST       |
| FF30 8601   |        | LDA A | #01     |                                |
| FF32 9739   |        | STA A | 39H     |                                |
| FF34 9627   |        | LDA A | 27H     |                                |
| FF36 9037   |        | SUB A | 37H     |                                |
| FF38 973A   |        | STA A | 3AH     | ;DELAY TIME (LO)               |
| FF3A 9626   |        | LDA A | 26H     |                                |
| FF3C 9238   |        | SBC A | 38H     |                                |
| FF3E 973B   |        | STA A | 3BH     | ;DELAY TIME (HI)               |
| FF40 9649   | TEMP1  | LIA A | 49H     |                                |
| FF42 8101   |        | CMP A | #01     |                                |
| FF44 2602   |        | ENE   | TEMP    | ;BRANCH UNLESS IN NO-TEMP MODE |
| FF46 201E   |        | BRA   | FINIS   |                                |
| FF48 9639   | TEMP   | LDA A | 39H     |                                |
| FF4A 8102   |        | CMP A | #02     |                                |
| FF4C 2702   |        | BEQ   | TEMP2   | ;BRANCH IF TIME > 73 SEC       |
| FF4E 201E   |        | BRA   | GOECK   |                                |
| FF50 8603   | TEMP2  | LDA A | #0C3H   |                                |
| FF52 B71340 |        | STA A | PAD     | ;ENABLE PK LET COMPARATOR      |
| FF55 8600   |        | LIA A | #00     |                                |
| FF57 9714   |        | STA A | 14H     |                                |
| FF59 9715   |        | STA A | 15H     |                                |
| FF5B 81FC37 |        | JSR   | AVG8    |                                |
| FF5E 9614   |        | LDA A | 14H     |                                |
| FF60 9717   |        | STA A | 17H     | ;STORE PEAK TEMP (LO)          |
| FF62 9615   |        | LIA A | 15H     |                                |
| FF64 9723   |        | STA A | 23H     | ;STORE PEAK TEMP (HI)          |
| FF66 9653   | FINIS  | LIA A | #53H    |                                |
| FF68 B71340 |        | STA A | PAD     | ;TURN OFF TESTING LED          |
| FF6E 9742   |        | STA A | 42H     |                                |
| FF6D 7EFB65 |        | JMP   | KEYIN   |                                |
| FE3E        | LIMP   | EQU   | 0FB0C8H |                                |
| FA40        | TEMP   | EQU   | 0FA40H  |                                |
| FC37        | AVG8   | EQU   | 0FC37H  |                                |
| F828        | NETTST | EQU   | 0F828H  |                                |
| 1340        | PAD    | EQU   | 1340H   |                                |
| FB65        | KEYIN  | EQU   | 0FB65H  |                                |
|             |        | END   |         |                                |





```

FB43 FB43 > ORG 0FB43H
FB43 0E PWRUP CLI
FB44 8060 LDA A #60H
FB46 F71345 STA A 1345H ;DISABLE NMI FROM TIMER
FB49 E71343 STA A 1343H ;SET DATA DIR REG B FOR INPUT
FB4C 8000 LIA A #00H
FB4E 9744 STA A 44H
FB50 9749 STA A 49H
FB52 807F LIA A #07FH
FB54 9745 STA A 45H
FB56 9E44 LDS 44H ;SET STACK POINTER TO 007F
FB58 86FF LDA A #0FFH
FB5A B71341 STA A 1341H ;SET DATA DIR REG A FOR OUTPUT
FB5D B1FC8B > JSR ZERO ;CLEAR ALL RAM
FB60 8613 LIA A #13H
FB62 9742 STA A 42H
FB64 01 NOP
FB65 9646 KEYIN LDA A 46H
FB67 9149 CMP A 49H ;HAS MOIE SET FROM
FB69 2602 BNE KEYACT ;KEYBOARD CHANGED?
FB6B 2078 BRA KEYIN ;IF NO, DO NOTHING
FB6D 9749 KEYACT STA A 49H ;IF YES, JUMP TO RESPONSE
FB6F 9E49 ADD A 49H
FB71 9B49 ADD A 49H
FB73 9731 STA A 31H ;LOAD OFFSET FOR JUMP
FB75 86FC LIA A #0FCH
FB77 973C STA A 3CH ;LOAD BASE ADDRESS FOR JUMP
FB79 LE3C LDX 3CH ;JUMP TO MOIE ROUTINE
FB7B 6E00 JMP X ;VECTOR TAIL
FC8B FC8B > ORG 0FC8BH
FC8B 8000 ZERO LDA A #00
FC8D 9740 STA A 40H
FC8F 9741 STA A 41H
FC91 B0FF70 JSR HEXPCD ;ZERO LCD
FC94 CE0049 LLX #49H
FC97 8600 LDA A #00
FC99 A700 CLEAR STA A X ;CLEAR ZERO-PAGE RAM
FC9B 09 DEX
FC9C 26FE BNE CLEAR
FC9E CE5FFF LLX #5FFFH
FCA1 8000 LIA A #00
FCA3 A700 CLR2 STA A X ;CLEAR DYNAMIC RAM
FCA5 LF19 STX 19H
FCA7 09 DEX
FCA8 9619 LDA A 19H
FCAA C61F LDA B #1FH
FCAC 11 CBA
FCAD 2704 BEQ CLR3
FCAF 8000 LIA A #00
FCB1 20F0 BRA CLR2
FCB3 904E CLR3 LIA A 4EH
FCB5 C60F LLA B #0FH
FCB7 11 CBA ;TEST IF CALIBRATED
FCB8 2604 BNE CLR1 ;IF YES,
FCBA 9643 LIA A #43H ;TURN ON CALIB & CLR LED
FCBC 2002 BRA DISP ;IF NO,
FCCE 8013 CLR1 LIA A #13H ;TURN ON CLR LED
FCC0 E71340 DISP STA A PAL
FCC3 9742 STA A 42H
FCC5 B71345 STA A 1345H ;TURN OFF TIMER NMI
FCC8 39 RTS

```



|      |        |              |        |                         |
|------|--------|--------------|--------|-------------------------|
| FF70 | 8600   | ORG          | 0FF70H |                         |
| FF72 | 973E   | HEXLCD LDA A | #20    | ;CLEAR OUTPUT           |
| FF74 | 973F   | STA A        | 3EH    | ;PCD OUTPUT (HI)        |
| FF76 | C610   | STA A        | 3FH    | ;PCD OUTPUT (LO)        |
| FF78 | D747   | LDA B        | #16    |                         |
| FF7A | 8626   | STA B        | 47H    |                         |
| FF7C | 9041   | LDA A        | #26H   |                         |
| FF7E | 2C08   | SUB A        | 41H    |                         |
| FF80 | E627   | BGE          | SHIFT  |                         |
| FF82 | 9741   | LDA A        | #27H   | ;IF INPUT WILL CAUSE    |
| FF84 | E60F   | STA A        | 41H    | ;OVERFLOW, THEN MAKE    |
| FF86 | 9740   | LDA A        | #2FH   | ;OUTPUT = 9999          |
| FF88 | 780040 | STA A        | 40H    |                         |
| FF8B | 790041 | SHIFT ASL    | 40H    | ;HEX INPUT (LO)         |
| FF8E | C00001 | ROL          | 41H    | ;HEX INPUT (HI)         |
| FF91 | 8600   | LDX          | #01    |                         |
| FF93 | 49     | DOUBL LDA A  | #00    |                         |
| FF94 | A93E   | ROL A        |        | ;PUTS CARRY BIT IN A    |
| FF96 | 19     | ADC A        | 3EH,X  |                         |
| FF97 | 2408   | DAA          |        |                         |
| FF99 | AB3E   | BCC          | SIDE   |                         |
| FF9B | 19     | ADD A        | 3EH,X  |                         |
| FF9C | A73E   | DAA          |        |                         |
| FF9E | 01     | STA A        | 3EH,X  |                         |
| FF9F | 2005   | SEC          |        |                         |
| FFA1 | A93E   | BRA          | DECR   |                         |
| FFA3 | 19     | SIDE ADC A   | 3EH,X  |                         |
| FFA4 | A73E   | DAA          |        |                         |
| FFA6 | 09     | STA A        | 3EH,X  |                         |
| FFA7 | 1F19   | DECR DEX     |        |                         |
| FFA9 | 2CE6   | STX          | 19H    |                         |
| FFAB | 7A0047 | BGE          | DOUBL  |                         |
| FFAE | 2E18   | DEC          | 47H    |                         |
| FFB0 | C00002 | BGT          | SHIFT  |                         |
| FFB3 | 8604   | LDX          | #02    | ;STORES OUTPUT IN LCD   |
| FFB5 | 9743   | LDA A        | #04H   | ;OUTPUT LATCHES         |
| FFB7 | A63D   | STA A        | 43H    |                         |
| FFB9 | 84F0   | OUT LDA A    | 3EH,X  |                         |
| FFBB | 9A43   | ANL A        | #0F0H  |                         |
| FFBD | E71340 | ORA A        | 43H    | ;ADIS LATCH MUX CONTRCL |
| FFC0 | 86FF   | STA A        | PAL    | ;LIGITS 2 THEN 4        |
| FFC2 | 4A     | LDA A        | #0FFH  |                         |
| FFC3 | 25F1   | SEND DEC A   |        |                         |
| FFC5 | A631   | BNE          | SEND   |                         |
| FFC7 | 48     | LDA A        | 31H,X  |                         |
| FFC8 | 48     | ASL A        |        |                         |
| FFC9 | 48     | ASL A        |        |                         |
| FFCA | 48     | ASL A        |        |                         |
| FFCB | 7C0043 | INC          | 43H    |                         |
| FFCE | 9743   | ORA A        | 43H    |                         |
| FFD0 | E71340 | STA A        | PAL    | ;LIGITS 1 THEN 3        |
| FFD3 | 86FF   | LDA A        | #0FFH  |                         |
| FFD5 | 4A     | SEND1 DEC A  |        |                         |
| FFD6 | 26F1   | BNE          | SEND1  |                         |
| FFD8 | 7C0043 | INC          | 43H    |                         |
| FFDB | 09     | LEX          |        |                         |
| FFDC | 2619   | BNE          | OUT    |                         |
| FFDE | 29     | RTS          |        |                         |
| 1340 | PAL    | EQU          | 1340H  |                         |
|      |        | END          |        |                         |



|      |        |        |                   |        |                         |
|------|--------|--------|-------------------|--------|-------------------------|
| FAB0 | FAB0   | >      | ORG               | 0FAB0H |                         |
| FAB0 | CE01F4 |        | <b>IRQRES</b> LDX | #500   |                         |
| FAB3 | 01     |        | WAIT NOP          |        |                         |
| FAB4 | 09     |        | LEX               |        |                         |
| FAB5 | 26FC   |        | BNE WAIT          |        | ;DEBOUNCE KEYBOARD      |
| FAB7 | 86F3   |        | LIA A             | #0F3H  |                         |
| FAB9 | B71340 |        | STA A             |        | ;RESET IRQ FLIP-FLOP    |
| FABC | 9642   |        | LIA A             | 42H    |                         |
| FABE | B71340 |        | STA A             | PAD    | ;RESTORE LED OUTPUT     |
| FAC1 | B61342 |        | LIA A             | PEI    | ;INPUT KEYBOARD ENTRY   |
| FAC4 | 841E   |        | AND A             | #15H   | ;MASK OFF KEY BITS      |
| FAC6 | 44     |        | LSR A             |        |                         |
| FAC7 | 9746   |        | STA A             | 46H    |                         |
| FAC9 | 9646   |        | LDA A             | 46H    |                         |
| FACB | 2706   |        | BEQ TAKIN         |        | ;IF NOT STOP OR ZERO    |
| FACL | 810F   |        | CMP A             | #0FH   | ;COMMANDS, RETURN TO    |
| FACF | 2702   |        | BEQ TAKIN         |        | ;PROGRAM                |
| FAD1 | 2021   |        | ERA               | BACK   |                         |
| FAD3 | 9642   | TAKIN  | LDA A             | 42H    |                         |
| FAL5 | 8163   |        | CMP A             | #63H   | ;IS TEST LED ON?        |
| FAD7 | 26E7   |        | BNE TAK           |        |                         |
| FAL9 | 8653   |        | LIA A             | #53H   | ;IF YES, TURN OFF       |
| FALB | B71340 |        | STA A             | PAL    |                         |
| FADE | 9742   |        | STA A             | 42H    |                         |
| FAE0 | 32     | TAK    | PUL A             |        | ;IF STOP OR ZERO KEY    |
| FAE1 | 32     |        | PUL A             |        | ;WAS PRESSED, RETURN    |
| FAE2 | 32     |        | PUL A             |        | ;TO KEYIN ONLY          |
| FAE3 | 32     |        | PUL A             |        |                         |
| FAE4 | 32     |        | PUL A             |        |                         |
| FAE5 | 32     |        | PUL A             |        |                         |
| FAE6 | 32     |        | PUL A             |        |                         |
| FAE7 | 8665   |        | LIA A             | #65H   |                         |
| FAE9 | 36     |        | PSH A             |        |                         |
| FAEA | 86FB   |        | LDA A             | #0FBH  |                         |
| FAEC | 36     |        | PSH A             |        |                         |
| FAED | 8600   |        | LDA A             | #00    |                         |
| FAEF | 36     |        | PSH A             |        |                         |
| FAF0 | 36     |        | PSH A             |        |                         |
| FAF1 | 36     |        | PSH A             |        |                         |
| FAF2 | 36     |        | PSH A             |        |                         |
| FAF3 | 36     |        | PSH A             |        |                         |
| FAF4 | 3B     |        | PSH A             |        |                         |
|      | 1340   | BACK   | RTI               |        |                         |
|      | FF70   | PAD    | EQU               | 1340H  |                         |
|      | 1342   | HEXBCD | EQU               | 0FF70H |                         |
|      | FC68   | PED    | EQU               | 1342H  |                         |
| FC68 | 86F8   | >      | ORG               | 0FC68H |                         |
| FC6A | B71340 |        | LIA A             | #24H   |                         |
| FC6D | 9642   |        | STA A             | 1340H  | ;LOAD TIMER FOR 2 MSEC  |
| FC6F | 8A08   |        | LIA A             | 42H    |                         |
| FC71 | B71340 |        | ORA A             | #8     |                         |
| FC74 | CE000F |        | STA A             | PAD    | ;ENABLE RAM REFRESH     |
| FC77 | 09     |        | LLX               | #15    |                         |
| FC78 | 26FL   | WAIT   | LEX               |        |                         |
| FC7A | 9642   |        | BNE WAIT          |        | ;WAIT FOR RAM REFRESH   |
| FC7C | 94F7   |        | LIA A             | 42H    |                         |
| FC7E | B71340 |        | AND A             | #0F7H  |                         |
| FC81 | 9649   |        | STA A             | PAD    | ;STOP RAM REFRESH       |
| FC83 | 8007   |        | LIA A             | 49H    | ;WHAT MODE WAS SELECTED |
| FC85 | 2E03   |        | SUB A             | #7     | ;BY KEYBOARD?           |
| FC87 | BDFF00 |        | EGT               | BACK   |                         |
| FC8A | 3E     |        | JSR               | ADC12  | ;GO TO A/D IF REQUIRED  |
|      | 1340   | BACK   | RTI               |        |                         |
|      | FD00   | PAD    | EQU               | 1340H  |                         |
|      |        | ADC12  | EQU               | 0FD00H |                         |
|      |        |        | END               |        |                         |



|      |        |       |       |        |                                |
|------|--------|-------|-------|--------|--------------------------------|
| FA40 | 8600   | LTEMP | ORG   | 0FA40H |                                |
| FA42 | 9701   |       | LIA A | #00    | ;DISPIAY TEMP IN IEG C         |
| FA44 | 9703   |       | STA A | 01H    |                                |
| FA46 | 970A   |       | STA A | 0EH    | ;SET UP FOR DIVISION           |
| FA48 | 865B   |       | STA A | 0AH    |                                |
| FA4A | 901F   |       | LDA A | #5BH   |                                |
| FA4C | 970C   |       | SUB A | 1FH    |                                |
| FA4E | 8607   |       | STA A | 0CH    | ;CHANGE SIGN OF ADC            |
| FA50 | 9223   |       | LDA A | #07    |                                |
| FA52 | 970B   |       | SBC A | 23H    |                                |
| FA54 | 8617   |       | STA A | 0EH    |                                |
| FA56 | 970F   |       | LIA A | #31    |                                |
| FA58 | C10002 |       | STA A | 0FH    | ;31 TO DIVISOR                 |
| FA5B | 960C   | QUAI  | LDX   | #02    |                                |
| FA5D | 9B0C   |       | LIA A | 0CE    | ;QUAIRUPLE OUTPUT              |
| FA5F | 970C   |       | AIL A | 0CH    |                                |
| FA61 | 960E   |       | STA A | 0CE    |                                |
| FA63 | 990B   |       | LDA A | 0BH    |                                |
| FA65 | 970B   |       | ADC A | 0BE    |                                |
| FA67 | 9C0A   |       | STA A | 0BH    |                                |
| FA69 | 990A   |       | LDA A | 0AH    |                                |
| FA6B | 970A   |       | ADC A | 0AH    |                                |
| FA6D | 09     |       | STA A | 0AH    |                                |
| FA6E | 201B   |       | LDX   |        |                                |
| FA70 | B1F184 |       | BNE   | QUAI   |                                |
| FA73 | 960B   |       | JSR   | DVII   | ;CONVERT TEMP TO WHOLE DEGREES |
| FA75 | 9741   |       | LDA A | 0EH    | ;BY DIVIDING A/D COUNT         |
| FA77 | 960C   |       | STA A | 41H    | ;BY 7.75                       |
| FA79 | 9740   |       | LDA A | 0CE    |                                |
| FA7B | B1FF70 |       | STA A | 40H    |                                |
| FA7D | 7E7B65 |       | JSR   | HEXBCE | ;DISPLAY PEAK TEMPERATURE      |
|      | FA00   |       | JMP   | KEYIN  |                                |
|      |        |       | ORG   | 0FA00H |                                |
| FA00 | 9621   | LTEST | LIA A | 21H    | ;PEAK THRUST IN 2.1N           |
| FA02 | 9706   |       | STA A | 2EH    | ;FMAX (LO) TO MPCAND           |
| FA04 | 962C   |       | LIA A | 2CH    |                                |
| FA06 | 9726   |       | STA A | 0EH    | ;FMAX (HI) TO MPCAND           |
| FA08 | 8664   |       | LIA A | #120   |                                |
| FA0A | 9704   |       | STA A | 04H    | ;MULTIPLIER = 100              |
| FA0C | 8600   |       | LDA A | #00    |                                |
| FA0E | 9702   |       | STA A | 02H    |                                |
| FA10 | 9703   |       | LDA A | 03H    |                                |
| FA12 | 9701   |       | STA A | 0DE    |                                |
| FA14 | B1F1CF |       | JSR   | MULT   | ;MULTIPLY FMAX BY 100          |
| FA17 | 9602   |       | LDA A | 0CH    |                                |
| FA19 | 970A   |       | STA A | 0AH    | ;PRODUCT TO DIVIDEND HI        |
| FA1B | 9603   |       | LDA A | 03H    |                                |
| FA1D | 9701   |       | STA A | 0FH    | ;DIVIDEND (MEI)                |
| FA1F | 9601   |       | LIA A | 04H    |                                |
| FA21 | 970C   |       | STA A | 0CH    | ;DIVIDEND (LO)                 |
| FA23 | 9C1A   |       | LIA A | 4AH    |                                |
| FA25 | 9707   |       | STA A | 0FH    | ;CALIB TO DIVISOR (LO)         |
| FA27 | 964E   |       | LIA A | 4EH    |                                |
| FA29 | 970E   |       | STA A | 0EH    | ;CALIB TO DIVISOR (MED)        |
| FA2B | B1F184 |       | JSR   | DVID   | ;DIVIDE PRODUCT BY 10 N.       |
| FA2E | 960C   |       | LIA A | 0CE    | ;DISPLAY PEAK THRUST           |
| FA30 | 9740   |       | STA A | 40H    | ;FMAX (LO) TO HEXBCD           |
| FA32 | 960E   |       | LIA A | 0EH    |                                |
| FA34 | 9741   |       | STA A | 41H    | ;FMAX (HI) TO HEXBCD           |
| FA36 | B1FF70 |       | JSR   | HEXBCE |                                |
| FA39 | 7E7B65 |       | JMP   | KEYIN  |                                |
|      | F184   | DVID  | EQU   | 0F184H |                                |
|      | F1CF   | MULT  | EQU   | 0F1CFH |                                |





|      |        |   |             |       |        |                                |
|------|--------|---|-------------|-------|--------|--------------------------------|
| FD84 | CE0019 | > | <b>EVID</b> | ORG   | 0FL84H |                                |
| FD87 | 9620   |   |             | LIX   | #25    |                                |
| FD89 | 9707   |   |             | LIA A | #00    |                                |
| FD8B | 9708   |   |             | STA A | 07     | ;CLEAR UPPER DIVIVILEND        |
| FD8D | 9709   |   |             | STA A | 08     |                                |
| FD8F | 9609   |   | UNSDV1      | STA A | 09     |                                |
| FL91 | 9712   |   |             | LDA A | 09     | ;SUETRACT DIVISOR FROM         |
| FL93 | 900F   |   |             | STA A | 12H    | ;UPPER DIVIDEND                |
| FL95 | 9709   |   |             | SUB A | 07H    |                                |
| FL97 | 9608   |   |             | STA A | 09     |                                |
| FD99 | 9711   |   |             | LCA A | 08H    |                                |
| FL9B | 920E   |   |             | STA A | 11H    |                                |
| FL9D | 970E   |   |             | SEC A | 0EH    |                                |
| FL9F | 9607   |   |             | STA A | 08     |                                |
| FDA1 | 9710   |   |             | LDA A | 07     |                                |
| FDA3 | 920L   |   |             | STA A | 10H    |                                |
| FDA5 | 9707   |   |             | SBC A | 01H    |                                |
| FDA7 | 240F   |   |             | STA A | 07H    |                                |
| FDA9 | 9610   |   |             | BCC   | UNSLV2 | ;BRANCH IF NO OVERFLOW         |
| FLAB | 9707   |   |             | LDA A | 10H    | ;CANCEL SUBTRACT IF OVERFLOW   |
| FLAD | 9611   |   |             | STA A | 07     |                                |
| FLAF | 9708   |   |             | LCA A | 11H    |                                |
| FLB1 | 9612   |   |             | STA A | 08     |                                |
| FDB3 | 9709   |   |             | LCA A | 12H    |                                |
| FLB5 | 0C     |   |             | STA A | 09     |                                |
| FLB6 | 2001   |   |             | CLC   |        | ;PUT A 0 IN QUOTIENT           |
| FDB8 | 0D     |   |             | BRA   | UNSLV3 |                                |
| FLB9 | 79000C |   | UNSDV2      | SEC   |        | ;PUT A 1 IN QUOTIENT           |
| FDBC | 79000B |   | UNSLV3      | ROL   | 0CH    |                                |
| FLBF | 79000A |   |             | ROL   | 0EH    |                                |
| FLC2 | 790009 |   |             | ROL   | 0AH    |                                |
| FDC5 | 790008 |   |             | ROL   | 09     |                                |
| FDC8 | 790007 |   |             | ROL   | 08     |                                |
| FLCB | 09     |   |             | ROL   | 07     | ;ROTATE DIVILEND LEFT          |
| FLCC | 25C1   |   |             | LEX   |        | ;TEST COUNTER                  |
| FLCE | 39     |   |             | ENE   | UNSLV1 |                                |
|      |        |   |             | RTS   |        |                                |
|      |        |   |             | END   |        |                                |
| FDCF |        | > | <b>MULT</b> | ORG   | 0FDCFH |                                |
| FDCF | 8600   |   |             | LCA A | #00    |                                |
| FLI1 | 9700   |   |             | STA A | 00     |                                |
| FLI3 | 9701   |   |             | STA A | 01     |                                |
| FDD5 | CE0019 |   | UNSM0       | LDX   | #25    | ;SET ITERATION COUNTER         |
| FLI8 | 0C     |   |             | CLC   |        |                                |
| FLI9 | 760000 |   | UNSM1       | ROR   | 00     |                                |
| FDDC | 760001 |   |             | ROR   | 01     |                                |
| FLIF | 760002 |   |             | ROR   | 02     |                                |
| FLI2 | 760003 |   |             | ROR   | 03     |                                |
| FDE5 | 760004 |   |             | ROR   | 04     |                                |
| FLI8 | 09     |   |             | LEX   |        | ;DECREMENT COUNTER             |
| FDE9 | FF19   |   |             | STX   | 19H    |                                |
| FLI3 | 2712   |   |             | BFQ   | UNSM2  | ;TEST COUNTER                  |
| FLI5 | 24EA   |   |             | BCC   | UNSM1  | ;BRANCH IF MULTIPLIER BIT IS 0 |
| FLIF | 9601   |   |             | LCA A | 01     | ;ADD MULTIPLICAND IF           |
| FLF1 | 0C     |   |             | CLC   |        | ;MULTIPLIER BIT IS 1           |
| FLF2 | 9906   |   |             | ADC A | 06     |                                |
| FDFA | 9701   |   |             | STA A | 01     |                                |
| FLF6 | 9600   |   |             | LCA A | 00     |                                |
| FLF8 | 9905   |   |             | ADC A | 05     |                                |
| FDFA | 9700   |   |             | STA A | 00     |                                |
| FLFC | 7EFF19 | > | UNSM2       | JMP   | UNSM1  |                                |
| FLFF | 39     |   |             | RTS   |        |                                |
|      |        |   |             | END   |        |                                |



```

FC15 > CALIB ORG 0FC15H
FCD5 3F SWI
FC16 B1FC37 JSR AVGE ;STORES ADC OUTPUT
FC19 9614 LDA A 14H ;FOR 10N INPUT
FC1B 904C SUB A 4CH ;SUBTRACT CALIB ZERO REF (LO)
FC1D 974A STA A 4AH ;CALIBRATION (LO)
FC1F 9615 LIA A 15H
FCE1 924D SBC A 41H ;SUBTRACTS CALIB ZERO REF (HI)
FCE3 974E STA A 4EH ;CALIBRATION (HI)
FCE5 9642 LIA A 42H
FCE7 81B3 CMP A #0E3H ;LIGHT UP CALIB LED
FCE9 2704 BEQ SET6 SET6
FCEB 8643 SET4 LDA A #43H
FCEL 2702 BRA PUT0 PUT0
FCEF 8663 SET6 LIA A #63H
FCF1 B71340 PUT0 STA A PAD
FCF4 9742 STA A 42H
FCF6 860F LIA A #0FH
FCF8 974E STA A 4EH ;SET CALIBRATION INDICATOR
FCFA B71345 STA A 1345H ;DISABLE NMI
FCFD 7EFB65 JMP KEYIN
FB31 > CALSET ORG 0FB31H
FB31 3F SWI
FB32 B1FC37 JSR AVGE ;STORES ADC OUTPUT
FB35 9014 LDA A 14H ;FOR ZERO WEIGHT
FB37 974C STA A 4CH ;CALIB ZERO REF (LO)
FB39 9615 LIA A 15H
FB3B 974D STA A 4DE ;CALIB ZERO REF (HI)
FB3D B71345 STA A 1345H ;DISABLE NMI
FB40 7EFB65 JMP KEYIN
FE65 KEYIN EQU 0FE65H
FC37 AVGE EQU 0FC37H
1340 PAD EQU 1340H
END
FC00 > VECTOR ORG 2FC00H
FC00 7EFB65 JMP 0FE65H ;KEYIN
FC03 7EFE00 JMP 0FE00H ;OPER (NO TEMP)
FC06 7EFE00 JMP 0FE00H ;OPER
FC09 7EFB31 JMP 0FE31H ;CALSET
FC0C 7EFC15 JMP 0FC15H ;CALIB
FC0F 7EFBA0 JMP 0FBA0H ;DDTHST
FC12 7EFBAC JMP 0FBACH ;IDTEMP
FC15 7EFA00 JMP 0FA00H ;DTHST
FC18 7EFEC8 JMP 0FFC9E ;LIMP
FC1B 7EFE00 JMP 0FR00H ;DDTIM
FC1E 7EFB24 JMP 0FE24H ;LTV
FC21 7EFA40 JMP 0FA40H ;DTEMP
FC24 7EF800 JMP 0F800H ;(APCOR)
FC27 7EF900 JMP 0F900H ;LOSC)
FC2A 7EFB24 JMP 0FB24H ;DDTIM
FC2D B1FC8B JSR 0FC8BH ;ZERO
FC30 7EFB65 JMP 0FE65H
FFF8 > ORG 0FFF8H
FFF8 FAF0 WORD 0FAB0H ;IRC VECTOR
FFFA FC68 WORD 2FC68H ;SWI VECTOR
FFFC FC68 WORD 2FC68H ;NMI VECTOR
FFFE FB43 WORD 0FB43H ;STARTUP VECTOR
END

```



|              |              |       |        |                                |
|--------------|--------------|-------|--------|--------------------------------|
| FEC8         | >            | ORG   | 0FEC8H |                                |
| FBC8 9632    | <b>LIMP</b>  | LDA A | 32H    | ; COMPUTES & DISPLAYS IMPULSE  |
| FBCA 9E32    |              | ADD A | 32H    | ; DOUBLE IMPULS                |
| FBCC 970C    |              | STA A | 00H    |                                |
| FCE8 9633    |              | LDA A | 33H    |                                |
| FBI0 9933    |              | ADC A | 33H    |                                |
| FBD2 970B    |              | STA A | 03H    |                                |
| FBI4 9634    |              | LDA A | 34H    |                                |
| FBI6 9934    |              | ADC A | 34H    |                                |
| FBD8 972A    |              | STA A | 0AH    | ; STORE IMPULS IN DIVIDEND     |
| FBI A 964A   |              | LDA A | 4AH    |                                |
| FBD C 970F   |              | STA A | 0FH    |                                |
| FBI E 964B   |              | LDA A | 4BH    |                                |
| FBE0 970E    |              | STA A | 0EH    | ; STORE CALIBRATION IN DIVISOR |
| FBE2 8600    |              | LDA A | #00    |                                |
| FBE4 9701    |              | STA A | 01H    |                                |
| FBE6 B1F184  |              | JSR   | IVIL   | ; PERFORM DIVISION TO GET      |
| FBE8 960B    |              | LDA A | 0BH    | ; UNITS OF .01 N-SEC           |
| FBEB 9741    |              | STA A | 41H    |                                |
| FBEI 960C    |              | LDA A | 0CH    |                                |
| FBEF 9740    |              | STA A | 40H    | ; CONVERT QUOTIENT TO BCD      |
| FBF1 B1FF70  |              | JSR   | HEXBCD | ; AND DISPLAY                  |
| FBF4 9649    |              | LDA A | 49H    |                                |
| FBF6 8002    |              | SUB A | #2     |                                |
| FBFB 2E03    |              | EGT   | E03    |                                |
| FBFA 7EFFF17 |              | JMP   | TEST3  |                                |
| FBFD 7EFE65  | BCK          | JMP   | KEYIN  |                                |
| FL00         | >            | ORG   | 2FE00H |                                |
| FB00 9637    | <b>IBTIM</b> | LDA A | 37H    | ; CONVERT BURN TIME            |
| FB02 970C    |              | STA A | 0CH    | ; INTERVAL COUNT               |
| FB04 9638    |              | LDA A | 38H    |                                |
| FB06 970B    |              | STA A | 0BH    | ; MOVE BURN TIME TO DIVIDEND   |
| FB08 8605    | SETUP        | LDA A | #05    |                                |
| FB0A 970F    |              | STA A | 0FH    | ; DIVISOR=5                    |
| FB0C 8600    |              | LDA A | #00    | ; CLEAR OTHER DIVISION BYTES   |
| FB0E 970F    |              | STA A | 0FH    |                                |
| FB10 970E    |              | STA A | 0EH    |                                |
| FB12 970A    |              | STA A | 0AH    |                                |
| FB14 B1F184  |              | JSR   | DVID   |                                |
| FB17 962C    |              | LDA A | 0CH    |                                |
| FB19 9740    |              | STA A | 40H    |                                |
| FB1B 960E    |              | LDA A | 0EH    |                                |
| FB1D 9741    |              | STA A | 41H    |                                |
| FB1F B1FF70  |              | JSR   | HEXBCD | ; DISPLAY TIME IN HUNDRETHS    |
| FE22 200A    |              | ERA   | 00EK   | ; OF A SECOND                  |
| FB24 963A    | <b>LTIM</b>  | LDA A | 3AH    | ; CONVERT DELAY TIME           |
| FB26 970C    |              | STA A | 0CH    | ; INTERVAL COUNT               |
| FB28 963B    |              | LDA A | 3BH    |                                |
| FE2A 970E    |              | STA A | 0EH    | ; MOVE DELAY TIME TO DIVIDEND  |
| FB2C 20LA    |              | BRA   | SETUP  |                                |
| FB2E 7EFL65  | GOFK         | JMP   | KEYIN  |                                |
| FF17         | TEST3        | LQU   | 0FF17H |                                |
| FF70         | HEXBCD       | ECU   | 0FF70H |                                |
| FB65         | KEYIN        | ECU   | 0FB65H |                                |
| FL84         | LVIL         | ECU   | 0FL84H |                                |
|              |              | END   |        |                                |



|             |        |       |        |                                 |
|-------------|--------|-------|--------|---------------------------------|
| F828        |        | ORG   | 0F828H |                                 |
| F829 9624   | NETTST | LDA A | 24H    |                                 |
| F82A 9614   |        | SUB A | 14H    |                                 |
| F82C 9717   |        | STA A | 17H    | ;NET THRUST LOW BYTE            |
| F82E 84F0   |        | ANL A | #0F0H  |                                 |
| F830 9721   |        | STA A | 21H    | ;UNPACKED NET THRUST MED BYTE   |
| F832 9625   |        | LDA A | 25H    |                                 |
| F834 9215   |        | SEC A | 15H    |                                 |
| F83C 9718   |        | STA A | 18H    | ;NET THRUST HIGH BYTE           |
| F839 8480   |        | ANL A | #80H   |                                 |
| F83A 8180   |        | CMP A | #60H   |                                 |
| F83C 2008   |        | BNE   | NET    |                                 |
| F83E 8600   |        | LDA A | #00    | ;MAKES NET THRUST ZERO          |
| F840 9717   |        | STA A | 17H    | ;IF NEGATIVE                    |
| F842 9718   |        | STA A | 18H    |                                 |
| F844 9721   |        | STA A | 21H    |                                 |
| F846 C82004 | NET    | LIX   | #04    |                                 |
| F849 9617   |        | LIA A | 17H    |                                 |
| F84B 1818   |        | LDA B | 18H    |                                 |
| F84L 48     | UNPCK  | ASL A |        |                                 |
| F84E 58     |        | ASL B |        |                                 |
| F84F 08     |        | DEX   |        |                                 |
| F850 1F19   |        | STX   | 19H    |                                 |
| F852 2EF9   |        | BGT   | UNPCK  |                                 |
| F854 9720   | BACK   | STA A | 20H    | ;UNPACKED NET THRUST LOW BYTE   |
| F856 1722   |        | STA B | 22H    | ;UNPACKED NET THRUST HI BYTE    |
| F858 39     |        | RTS   |        |                                 |
|             |        | END   |        |                                 |
| F8A0        |        | ORG   | 0F8A0H |                                 |
| F8A0 96C3   | DETHST | LIA A | #013H  | ;ENABLE THRUST COMPARATOR       |
| F8A2 F71340 |        | STA A | PAL    |                                 |
| F8A5 9642   |        | LIA A | 42H    |                                 |
| F8A7 E71340 |        | STA A | PAD    |                                 |
| F8AA 200A   |        | BCA   | ATOL   |                                 |
| F8AC 8603   | ELTEMP | LIA A | #0C3H  | ;ENABLE THERMOCOUPLE COMPARATOR |
| F8AE F71340 |        | STA A | PAL    |                                 |
| F8B1 9642   |        | LIA A | 42H    |                                 |
| F8B3 F71340 |        | STA A | PAD    |                                 |
| F8B6 EDFD00 | ATOL   | JSR   | ADC12  |                                 |
| F8B8 9624   |        | LDA A | 24H    |                                 |
| F8BB 9740   |        | STA A | 40H    | ;LOW ADC TO HEXBCD              |
| F8BD 9625   |        | LDA A | 25H    |                                 |
| F8BF 9741   |        | STA A | 41H    | ;HIGH ADC TO HEXBCD             |
| F8C1 BDF70  |        | JSR   | HEXPC1 |                                 |
| F8C4 7E7B65 |        | JMP   | KEYIN  |                                 |
| F870        | HEXPCD | EQU   | 0FF70H |                                 |
| F865        | KEYIN  | EQU   | 0F165H |                                 |
| 1146        | PAL    | EQU   | 1140H  |                                 |
| 1120        | ADC12  | EQU   | 2F102H |                                 |
|             |        | END   |        |                                 |





## LIST OF REFERENCES

1. Ott, H.W., Noise Reduction Techniques in Electronic Systems, John Wiley, 1976.
2. Cook, N.H., and Rabinowicz, E., Physical Measurement and Analysis, pp. 125-134, Addison-Wesley, 1963.
3. Baumeister, I., and Marks, L., Standard Handbook for Mechanical Engineers, 7th ed., pp. 5-30 - 5-104, McGraw-Hill, 1967.
4. Wait, J.V., Huelsman, L.P., and Korn, G.A., Introduction to Operational Amplifier Theory and Applications, McGraw-Hill, 1975.
5. National Semiconductor Corp., Linear Applications Handbook, vol. 1, 1977.
6. Analog Devices, Inc., Data Acquisition Products Catalog, 1978.
7. Millman, J., and Halkias, C.C., Integrated Electronics, pp. 549-553, McGraw-Hill, 1972.
8. Miller, J.T., The Instrument Manual, pp. 210-264, United Trade Press, 1971.
9. Weast, R.C., Handbook of Chemistry and Physics, 49th ed., pp. E103-E111, Chemical Rubber Co., 1968.
10. Analog Devices, Inc., Analog-Digital Conversion Handbook, 1972.
11. Intel Corporation, Component Data Catalog, 1978.
12. Peatman, J.B., Microcomputer-Based Design, McGraw-Hill, 1977.



# INITIAL DISTRIBUTION LIST

|  | No. Copies |
|--|------------|
| 1. Defense Documentation Center<br>Cameron Station<br>Alexandria, Virginia 22314   | 2          |
| 2. Library, Code 0142<br>Naval Postgraduate School<br>Monterey, California 93940   | 2          |
| 3. Department Chairman, Code 62<br>Department of Electrical Engineering<br>Naval Postgraduate School<br>Monterey, California 93940             | 1          |
| 4. Assoc Professor M. L. Cotton, Code 62 Cc<br>Department of Electrical Engineering<br>Naval Postgraduate School<br>Monterey, California 93940 | 1          |
| 5. LT Arthur H. Barber III, USN<br>1408 N. Cascade Ave.<br>Colorado Springs, Colorado 80907  | 1          |



Thesis  
B2165  
c.1

Barber

Development of a  
microprocessor-based  
instrument for static  
testing small rocket  
engines.

104094

thesB2165

Development of a microprocessor-based in



3 2768 001 00689 3

DUDLEY KNOX LIBRARY